

DSC 2nd  
#32 POD

## Hydro Pumps, Inc.

6512 NW 13th Court  
Plantation, FL 33313

Broward: (954) 583-3303  
Fax: (954) 583-3305

Toll Free (FL) 1-800-306-7867

October 23, 2017

K W Resort Utilities Corp.  
PO Box 2125  
Key West, FL 33045

Attn: Greg Wright  
Re: LS2A Replacement - Control Panel

Gentlemen:

We offer the following equipment in reference to your inquiry:

- 1 – Duplex control panel rated 5hp, 230V, 3 phase which includes the following: NEMA 4X type 316 stainless steel enclosure, Square D QOU390 main & emergency circuit breakers, Crouse-Hinds AR1042S22 emergency generator receptacle, Square D QOU350 pump circuit breakers, Square D QOU115 control circuit breaker, duplex GFI receptacle with Square D QOU115 circuit breaker, IEC-rated motor starters with thermal overload mechanisms, high water alarm light and horn with silence and test, duplex alternator with mode selector, hand-off-auto switches, run lights, elapsed time meters and oil seal fail indication for each pump, lightning arrestor, surge arrestor, phase monitor and 120V 4-point float control circuit.

**TOTAL PRICE PUMP CONTROL PANEL \$ 5,947.**

Price quoted includes delivery to your Key West facility but does not include Florida State Sales Tax. Delivery is estimated at 4-6 weeks after receipt of order. Delivery is estimated at 4-6 weeks after receipt of approved shop drawings. If you have any questions or comments concerning this quotation, please call our office.

Sincerely,

Juli Robbins, PE

Digitally signed by Juli Robbins, PE  
DN: cn=Juli Robbins, PE, o=Hydro Pumps, Inc.,  
ou, email=hydro-pumps@att.net, c=US  
Date: 2017.10.23 16:15:54 -0400

KWRU 018165