



FILED 4/2/2024  
DOCUMENT NO. 01507-2024  
FPSC - COMMISSION CLERK

Attorneys and Counselors at Law  
123 South Calhoun Street  
P.O. Box 391 32302  
Tallahassee, FL 32301  
P: (850) 224-9115  
F: (850) 222-7560  
[ausley.com](http://ausley.com)

April 2, 2024

**ELECTRONIC FILING**

Mr. Adam J. Teitzman, Commission Clerk  
Office of Commission Clerk  
Florida Public Service Commission  
2540 Shumard Oak Boulevard  
Tallahassee, Florida 32399-0850

Re: Docket 20240026-EI; Petition for Rate Increase by Tampa Electric Company

Dear Mr. Teitzman:

Attached for filing on behalf of Tampa Electric Company in the above-referenced docket is the Direct Testimony of Jeff Kopp and Exhibit No. JK-1.

Thank you for your assistance in connection with this matter.

(Document 13 of 32)

Sincerely,

A handwritten signature in blue ink that reads 'J. Jeffrey Wahlen'.

J. Jeffrey Wahlen

cc: All parties

JJW/ne  
Attachment

BEFORE THE  
FLORIDA PUBLIC SERVICE COMMISSION

DOCKET NO. 20240026-EI  
IN RE: PETITION FOR RATE INCREASE  
BY TAMPA ELECTRIC COMPANY

PREPARED DIRECT TESTIMONY AND EXHIBIT  
OF  
JEFF KOPP

ON BEHALF OF  
TAMPA ELECTRIC COMPANY

1                                   **BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION**

2                                   **PREPARED DIRECT TESTIMONY**

3                                   **OF**

4                                   **JEFF KOPP**

5                                   **ON BEHALF OF TAMPA ELECTRIC COMPANY**

6  
7   **Q.**   Please state your name, address, occupation, and employer.

8  
9   **A.**   My name is Jeffrey (Jeff) T. Kopp, and my business address  
10       is 9400 Ward Parkway, Kansas City, Missouri 64114. I am  
11       employed by 1898 & Co., which is the consulting group  
12       within Burns & McDonnell Engineering Company, Inc. ("1898  
13       & Co."), as the Senior Managing Director of the Energy &  
14       Utilities Consulting Department.

15  
16   **Q.**   Please describe your duties and responsibilities in that  
17       position.

18  
19   **A.**   I am a professional engineer with 22 years of experience  
20       consulting to electric utilities. I have been involved in  
21       numerous decommissioning studies and served as project  
22       manager or project director on the majority of them. I have  
23       helped prepare decommissioning studies on all types of  
24       power plants, utilizing various technologies and fuels.

1 As a Senior Managing Director at 1898 & Co., I oversee a  
2 group of more than 250 engineers and consultants who provide  
3 consulting services to clients primarily in the electric  
4 power generation and electric power transmission  
5 industries, but also to other industrial and commercial  
6 clients. The services provided by this group of engineers  
7 and consultants include decommissioning cost studies,  
8 independent engineering assessments of existing power  
9 generation assets, economic evaluations of capital  
10 expenditures, new power generation development and  
11 evaluation, electric and water rate analysis, electric  
12 transmission planning, generation resource planning,  
13 renewable power development, and other related engineering  
14 and economic assessments.

15  
16 **Q.** Have you previously testified before the Florida Public  
17 Service Commission ("Commission")?  
18

19 **A.** Yes. I provided direct testimony on behalf of Tampa Electric  
20 Company ("Tampa Electric" or the "company") in Docket No.  
21 20210034-EI. I provided rebuttal testimony on behalf of  
22 Progress Energy Florida, Inc. in Docket No. 20090079-EI in  
23 support of the dismantlement study I prepared for Progress  
24 Energy Florida to support their depreciation rates in that  
25 filing. I also provided rebuttal testimony on behalf of

1 Florida Power & Light Company in Docket Nos. 20160021-EI  
2 and 20160062-EI and I am currently providing testimony on  
3 behalf of Duke Energy Florida in Docket No. 20240025-EI,  
4 and I did perform the dismantlement study that was included  
5 as an exhibit and approved as part of the settlement in  
6 Duke Energy Florida's prior rate case.

7  
8 **Q.** Have you previously testified before other state or federal  
9 regulatory commissions?

10  
11 **A.** Yes. I have provided written or oral testimony in various  
12 proceedings listed in Document No. 3 of my Exhibit No. JK-  
13 1.

14  
15 **Q.** Please provide a brief outline of your educational  
16 background and business experience.

17  
18 **A.** I have a Bachelor's Degree in Civil Engineering from the  
19 University of Missouri - Rolla (now the Missouri University  
20 of Science and Technology) and a Masters of Business  
21 Administration from the University of Kansas. In my role  
22 as a group manager, project manager, and project engineer,  
23 I have worked on and have overseen consulting activities  
24 for coal, natural gas, wind, solar, hydroelectric, and  
25 biomass power generation facilities. I have included my

1 resume and curriculum vitae as Document No. 2 of my  
2 exhibit.

3

4 **Q.** Do you hold any certifications?

5

6 **A.** Yes, I am a registered professional engineer in the states  
7 of Florida, Illinois, Indiana, and Missouri.

8

9 **Q.** What are the purposes of your direct testimony?

10

11 **A.** The purposes of my prepared direct testimony are to (1)  
12 discuss the Fleet Decommissioning Cost Study  
13 ("Dismantlement Study" or "the Study") conducted for Tampa  
14 Electric and (2) support the reasonableness of the  
15 Dismantlement Study costs included in the company's rate  
16 request. The Dismantlement Study is an update of a prior  
17 study that I prepared for Tampa Electric to support their  
18 filing in Docket No. 20210034-EI.

19

20 **Q.** Have you prepared an exhibit to support your direct  
21 testimony?

22

23 **A.** Yes. Exhibit No. JK-1 was prepared under my direction and  
24 supervision. My exhibit consists of three documents,  
25 entitled:

- 1 Document No. 1 Decommissioning Cost Estimate Study  
2 Document No. 2 Resume of Jeffrey Kopp  
3 Document No. 3 List of Proceedings in Which Mr. Kopp  
4 Has Submitted Testimony

5  
6 **Q.** Are you sponsoring any sections of Tampa Electric's  
7 Minimum Filing Requirement ("MFR") Schedules?

8  
9 **A.** No.

10  
11 **Q.** Which Tampa Electric generating units does the Study assume  
12 will be dismantled?

13  
14 **A.** The Study assumes that all units in Tampa Electric's  
15 generation fleet will be dismantled.

16  
17 **Q.** Are there other witnesses submitting direct testimony in  
18 this proceeding that addresses dismantlement costs for  
19 Tampa Electric, and if so, how does their testimony relate  
20 to your testimony?

21  
22 **A.** Yes. Tampa Electric witness Ned Allis is testifying to and  
23 sponsoring the depreciation rate calculations. The  
24 dismantlement costs that I prepared were used as an input  
25 for end-of-life costs in the depreciation calculations.

1 **1898 & CO. Experience & Qualifications**

2 **Q.** What qualifies 1898 & Co. to prepare accurate estimates of  
3 dismantlement costs and why should the Commission rely on  
4 these estimates?

5  
6 **A.** Over the years, 1898 & Co. has worked closely with  
7 demolition contractors in developing decommissioning cost  
8 estimates in order to more accurately estimate the costs  
9 for activities that the demolition contractors will  
10 perform. 1898 & Co. has prepared numerous decommissioning  
11 studies for various clients considering different  
12 technologies in several different states and has provided  
13 services to clients on decommissioning project execution  
14 that has included review and evaluation of bids from  
15 demolition contractors. 1898 & Co. has utilized this  
16 experience preparing decommissioning estimates as well as  
17 reviewing demolition contractor bids to confirm the  
18 reasonableness of the cost estimates prepared by 1898 & Co.

19  
20 At the time the company decides to decommission the plants,  
21 means and methods will not be dictated to the contractor by  
22 1898 & Co. It will be the contractor's responsibility to  
23 determine means and methods that result in safely  
24 decommissioning and dismantling the Plants at the lowest  
25 possible cost. However, based on 1898 & Co.'s experience



1 with decommissioning projects and discussions with  
2 demolition contractors, the costs estimated by 1898 & Co.  
3 are reflective of what contractors would bid, through a  
4 competitive bidding process given the option to select safe  
5 and efficient means and methods.

6  
7 As indicated above, 1898 & Co. has vast experience in  
8 preparation of decommissioning studies, overseeing  
9 demolition projects, and executing construction projects.  
10 In order to execute over \$2 billion of construction projects  
11 on an annual basis, 1898 & Co. has to win this work through  
12 competitive bidding processes, which requires us to be able  
13 to accurately prepare cost estimates. If we routinely  
14 estimated costs too high, we would not be successful in  
15 winning projects. If we routinely estimated costs too low,  
16 we would not be able to execute projects profitably and  
17 would no longer be active in this market.

18  
19 Our long history, large market presence, and top industry  
20 rankings demonstrate our ability to effectively and  
21 accurately estimate costs. In addition, we have seen  
22 competitive bids from demolition contractors for power  
23 plant demolition projects, and we have worked with  
24 demolition contractors over the years to refine our  
25 estimating process for decommissioning studies to align our

1 costs with theirs.

2

3 **1898 & CO. DISMANTLEMENT STUDY**

4 **Q.** Please describe the purpose of the Dismantlement Study.

5

6 **A.** The company retained 1898 & Co. to provide it with a  
7 recommendation regarding the total cost, in 2023 dollars,  
8 of dismantlement of each company-owned generation unit at  
9 the end of its useful life, as well as the total cost of  
10 dismantlement of the common facilities at these generating  
11 plants. The total dismantlement cost as determined by 1898  
12 & Co. and reflected in the Dismantlement Study is net of  
13 salvage value for scrap materials at each plant. 1898 & Co.  
14 had previously prepared a similar study for the company in  
15 2020 in support of the company's depreciation filing. The  
16 current Dismantlement Study serves to update the costs  
17 presented in the 2020 study for changes to market  
18 conditions, physical changes that have occurred at the  
19 plants, and incorporating new facilities that have been  
20 constructed or acquired since 2020.

21

22 **Q.** What plants did 1898 & Co. evaluate in the Dismantlement  
23 Study?

24

25 **A.** For purposes of the Dismantlement Study, we evaluated the

1 following company-owned electric generating and storage  
2 plants.

- 3 • Agrivoltaics Solar
- 4 • Alafia Solar
- 5 • Balm Solar
- 6 • Bayside Power Station
- 7 • Big Bend Power Station
- 8 • Big Bend Floating Solar
- 9 • Big Bend Solar
- 10 • Big Bend Solar II
- 11 • Bonnie Mine Solar
- 12 • Brewster Solar
- 13 • Bull Frog Creek Solar
- 14 • Cotton Mouth Ranch Solar
- 15 • Durrance Solar
- 16 • Eastern PVS and ES Solar
- 17 • English Creek Solar
- 18 • Florida Aquarium Pavilion Solar
- 19 • Future Solar Site I
- 20 • Future Solar Site II
- 21 • Grange Hall Solar
- 22 • Jamison Solar
- 23 • Juniper Solar
- 24 • Lake Hancock Solar
- 25 • Lake Mabel Solar

- 1 • Laurel Oaks Solar
- 2 • Legoland Solar
- 3 • Lithia Solar
- 4 • Little Manatee Solar
- 5 • MacDill Air Force Base RICE and Battery
- 6 • Magnolia Solar
- 7 • Mountain View Solar
- 8 • Payne Creek Solar
- 9 • Peace Creek Solar
- 10 • Polk Power Station
- 11 • Riverside Solar
- 12 • Tampa International Solar
- 13 • Wimauma Solar

14

15 **Q.** What was the extent of your personal involvement in the  
16 preparation of the Dismantlement Study?

17

18 **A.** I served as the 1898 & Co. BMCD project director on the  
19 Dismantlement Study. I worked directly with all individuals  
20 and parties involved in the preparation of the  
21 dismantlement cost estimates in the Dismantlement Study. I  
22 was responsible for the overall project and was involved in  
23 the development of the dismantlement assumptions,  
24 dismantlement estimating methodology, preparation and  
25 review of the estimates, and preparation and review of the

1 report.

2

3 **Q.** What was the extent of your personal involvement in the  
4 preparation of the prior Dismantlement Study prepared for  
5 Tampa Electric Company?

6

7 **A.** I also served as the 1898 & Co. project director on the  
8 prior study and testified to the reasonableness of those  
9 costs to support their filings in Docket No. 20210034-EI.

10

11 **Q.** Did individuals from 1898 & Co. visit each of the sites  
12 included in the Dismantlement Study?

13

14 **A.** No. In 2017, I visited a representative portion of sites  
15 for which dismantlement cost estimates were prepared as  
16 part of a prior study, along with other individuals from  
17 1898 & Co. and representatives from the company. As part of  
18 the current Dismantlement Study, individuals from my team  
19 re-visited a portion of these same sites and a  
20 representative portion of the solar sites.

21

22 **Q.** What level of dismantlement and demolition did 1898 & Co.  
23 assume was performed at each of the sites?

24

25 **A.** The basis of the 1898 & Co. cost estimates was that all

1 sites will be restored to an industrial condition, suitable  
2 for reuse for development of an industrial facility.

3

4 **Q.** What does restoring the sites for industrial use require?

5

6 **A.** The sites will have all above grade buildings and equipment  
7 removed, foundations removed to three feet below grade, be  
8 rough graded, and seeded. The sites also will have small  
9 diameter underground pipes capped and abandoned in place.  
10 The sites can remain in this condition in perpetuity, until  
11 the site is specifically redeveloped for industrial use.

12

13 **Q.** What process did you follow in preparing the Dismantlement  
14 Study?

15

16 **A.** The estimates of dismantlement costs were prepared with the  
17 intent of most accurately representing what 1898 & Co. would  
18 anticipate contractors bidding to dismantle the equipment,  
19 address environmental issues, and restore the site through  
20 a competitive bidding process.

21

22 As outlined in the Dismantlement Study, we prepared these  
23 cost estimates by estimating quantities and then applying  
24 current market pricing for labor rates, equipment costs,  
25 scrap, and disposal costs specific to the area in which the

1 work is to be performed. This results in the total cost of  
2 dismantlement for each site.

3  
4 **Q.** Are there industry-standard methods or inputs used when  
5 preparing such a study and what are they?

6  
7 **A.** Yes. We reviewed Rule 25-6.04364, Florida Administrative  
8 Code, Electric Utilities Dismantlement Studies, as a guide  
9 for preparing our study. We also incorporated the  
10 methodologies used in prior studies we prepared that have  
11 been approved by the Commission and other utility  
12 commissions throughout the country. Furthermore, many of  
13 the inputs in our estimates come directly from industry  
14 standard data sources and publications, including:

- 15 • RSMeans Heavy Construction Cost
  - 16 ○ RSMeans is an industry standard publication of
  - 17 construction cost data that is used throughout North
  - 18 America by engineers to prepare construction and
  - 19 demolition cost estimates. The RSMeans database
  - 20 includes adjustments to the base costs based on
  - 21 location, to provide a more accurate estimate for
  - 22 the area in which the project will take place.
  - 23 RSMeans includes data for all types of construction
  - 24 and demolition activities, including materials,
  - 25 labor, hauling, and disposal. RSMeans has been

1 publishing construction and demolition costs  
2 annually since the 1940s.

- 3 • Fastmarkets AMM
  - 4 o Fastmarkets AMM has been in business since they
  - 5 began as American Metal Market in 1882. They are
  - 6 the leading publication of metal pricing, including
  - 7 scrap metal pricing. They provide an independent
  - 8 market perspective on metal prices in North America,
  - 9 using data from market transactions.

10

11 **Q.** Did Tampa Electric provide data to you for use in the Study?

12

13 **A.** Yes.

14

15 **Q.** What data did the company provide?

16

17 **A.** The company provided numerous drawings for each of the sites  
18 evaluated in the Study. Other documents that had applicable  
19 requirements for decommissioning activities were provided  
20 as well.

21

22 **Q.** Please describe the key assumptions of the Dismantlement  
23 Study.

24

25 **A.** As I stated earlier, the basis of the estimates was that



1 all sites will be restored to an industrial condition,  
2 suitable for reuse for development of an industrial  
3 facility. We also assumed that all units at each power  
4 station will be dismantled as part of a single demolition  
5 project, therefore, no selective demolition was included in  
6 the estimates. Additional assumptions are outlined in  
7 Sections 3.1 and 3.2 of the Study in Document No. 1 of my  
8 exhibit.

9  
10 **Q.** Please generally explain the types of costs reflected in  
11 the Study?

12  
13 **A.** The cost estimates reflected in the Dismantlement Study are  
14 inclusive of direct costs associated with dismantling the  
15 plant equipment and facilities and restoring the sites to  
16 an industrial-ready condition. The direct costs include  
17 environmental remediation costs for asbestos removal and  
18 other hazardous material handling and disposal, as well as  
19 costs for removing and disposing of contaminated soil  
20 around transformers. The Dismantlement Study does not  
21 include any estimates of indirect costs to be incurred by  
22 the company during dismantlement, nor any contingency  
23 costs. Indirect owner's costs and contingency costs were  
24 applied by Tampa Electric separate from the Study.

25

1 Q. How were the direct costs estimated for purposes of the  
2 Study?

3

4 A. As part of the Dismantlement Study, site-specific cost  
5 estimates were developed using a "bottom-up" cost  
6 estimating approach, where cost estimates are developed  
7 from scratch through the development of site-specific  
8 quantity estimates and the application of unit pricing  
9 rates to the quantity estimates.

10

11 As outlined in the Dismantlement Study, 1898 & Co. prepared  
12 these cost estimates by estimating quantities for existing  
13 equipment based on visual inspections, review of  
14 engineering drawings, review of 1898 & Co.'s in-house  
15 database of plant equipment quantities and using 1898 &  
16 Co.'s professional judgment. This resulted in an estimate  
17 of quantities for the tasks required to be performed for  
18 each dismantlement effort. Current market pricing for labor  
19 rates and equipment was used to develop unit pricing rates  
20 for each task. These unit pricing rates were applied to the  
21 quantities for the plants to determine the total direct  
22 cost of dismantlement for each site. Additionally, unit  
23 pricing for scrap values was applied to the scrap quantities  
24 to determine anticipated salvage values, which were  
25 subtracted from the gross direct costs to arrive at a net

1 project cost in 2023 dollars.

2  
3 **Q.** Is it your conclusion that the Study results are reasonable  
4 estimates?

5  
6 **A.** Yes, the Dismantlement Study results and cost estimates are  
7 reasonable estimates and are useful for planning purposes.  
8 It is appropriate for the company to rely on these estimates  
9 for inclusion in their dismantlement reserve needs.

10  
11 **SUMMARY**

12 **Q.** Please summarize your direct testimony.

13  
14 **A.** The company retained 1898 & Co. to provide it with a  
15 recommendation regarding the total cost, in 2023 dollars,  
16 of dismantlement of each company-owned generation unit at  
17 the end of its useful life as well as the total cost of  
18 dismantlement of the common facilities at these generating  
19 plants. 1898 & Co. is qualified to prepare dismantlement  
20 cost estimates and has vast experience in preparing  
21 decommissioning studies, overseeing demolition projects,  
22 and executing construction projects. The estimates of  
23 dismantlement costs were prepared with the intent of most  
24 accurately representing what 1898 & Co. would anticipate  
25 contractors bidding through a competitive bidding process

1 to dismantle the equipment, address environmental issues,  
2 and restore the site. The Dismantlement Study is consistent  
3 with Rule 25-6.04364, Florida Administrative Code,  
4 Electric Utilities Dismantlement Studies, incorporates the  
5 methodologies used in prior studies we prepared that have  
6 been approved by the Commission and other utility  
7 commissions throughout the country, and incorporates  
8 industry standard data. The Study results and cost  
9 estimates are reasonable estimates and appropriate for the  
10 company to rely on for their dismantlement reserve needs.

11

12 **Q.** Was the Dismantlement Study attached to your testimony as  
13 Document No. 1 of your exhibit prepared by you or under  
14 your supervision?

15

16 **A.** Yes.

17

18 **Q.** Are the estimated costs reflected in the Dismantlement  
19 Study reasonably reflective of the actual costs necessary  
20 to dismantle the company's plants?

21

22 **A.** Yes, they are.

23

24 **Q.** Are these estimated costs appropriate for use in the  
25 development of dismantlement accrual for the company's

1 electric generating plants?

2

3 **A.** Yes.

4

5 **Q.** Does this conclude your direct testimony?

6

7 **A.** Yes, it does.

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

**EXHIBIT**

**OF**

**JEFF KOPP**

**ON BEHALF OF**

**TAMPA ELECTRIC COMPANY**

**Table of Contents**

<b>DOCUMENT NO.</b>	<b>TITLE</b>	<b>PAGE</b>
1	Decommissioning Cost Estimate Study	22
2	Resume of Jeffrey Kopp	88
3	List of Proceedings in Which Mr. Kopp Has Submitted Testimony	103



# TECO DECOMMISSIONING COST ESTIMATE STUDY

TAMPA ELECTRIC COMPANY

2023 FLEET DECOMMISSIONING STUDY  
162002

REVISION 2

November 28, 2023



## Disclaimer

1898 & Co.® is a part of Burns & McDonnell that performs or provides business, technology, and consulting services. 1898 & Co. does not provide legal, accounting, or tax advice. The reader is responsible for obtaining independent advice concerning these matters. That advice should be considered by reader, as it may affect the content, opinions, advice, or guidance given by 1898 & Co. Further, 1898 & Co. has no obligation and has made no undertaking to update these materials after the date hereof, notwithstanding that such information may become outdated or inaccurate. These materials serve only as the focus for consideration or discussion; they are incomplete without the accompanying oral commentary or explanation and may not be relied on as a stand-alone document.

The information, analysis, and opinions contained in this material are based on publicly available sources, secondary market research, and financial or operational information, or otherwise information provided by or through 1898 & Co. clients whom have represented to 1898 & Co. they have received appropriate permissions to provide to 1898 & Co., and as directed by such clients, that 1898 & Co. is to rely on such client-provided information as current, accurate, and complete. 1898 & Co. has not conducted complete or exhaustive research, or independently verified any such information utilized herein, and makes no representation or warranty, express or implied, that such information is current, accurate, or complete. Projected data and conclusions contained herein are based (unless sourced otherwise) on the information described above and are the opinions of 1898 & Co., which should not be construed as definitive forecasts and are not guaranteed. Current and future conditions may vary greatly from those utilized or assumed by 1898 & Co.

1898 & Co. has no control over weather; cost and availability of labor, material, and equipment; labor productivity; energy or commodity pricing; demand or usage; population demographics; market conditions; changes in technology, and other economic or political factors affecting such estimates, analyses, and recommendations. To the fullest extent permitted by law, 1898 & Co. shall have no liability whatsoever to any reader or any other third party, and any third party hereby waives and releases any rights and claims it may have at any time against 1898 & Co. and any Burns & McDonnell affiliated company, with regard to this material, including but not limited to the accuracy or completeness thereof.

Any entity in possession of, or that reads or otherwise utilizes information herein is assumed to have executed or otherwise be responsible and obligated to comply with the contents of any Confidentiality Agreement and shall hold and protect its contents, information, forecasts, and opinions contained herein in confidence and not share with others without prior written authorization.

## CONTENTS

---

1.0	Introduction	1
1.1	Background	1
1.2	Methodology	1
1.3	Site Visit	1
2.0	Plant Descriptions	3
2.1	Agrivoltaics	3
2.2	Alafia Solar	3
2.3	Balm Solar	3
2.4	Bayside Power Station	3
2.5	Big Bend Power Station	3
2.6	Big Bend Floating Solar	4
2.7	Big Bend Solar	4
2.8	Big Bend Solar II	4
2.9	Bonnie Mine Solar	4
2.10	Brewster Solar	4
2.11	Bull Frog Creek Solar	4
2.12	Cotton Mouth Ranch Solar	4
2.13	Durrance Solar	5
2.14	Eastern PVS+ES Solar	5
2.15	English Creek Solar	5
2.16	Florida Aquarium Pavilion	5
2.17	Future Solar Site I	5
2.18	Future Solar Site I	5
2.19	Grange Hall Solar	5
2.20	Jamison Solar	5
2.21	Juniper Solar	5
2.22	Lake Hancock Solar	6
2.23	Lake Mabel Solar	6
2.24	Laurel Oak Solar	6
2.25	Legoland Solar	6
2.26	Lithia Solar	6
2.27	Little Manatee Solar	6
2.28	MacDill AFB RICE/Battery	6
2.29	Magnolia Solar	6
2.30	Mountain View Solar	6
2.31	Payne Creek Solar	7
2.32	Peace Creek Solar	7
2.33	Polk Power Station	7
2.34	Riverside Solar	7

2.35	Tampa International Solar (TIA)	7
2.36	Wimauma Solar	7
<b>3.0</b>	<b>Decommissioning Costs</b>	<b>8</b>
3.1	General Assumptions Applicable to All Sites	9
3.2	Site Specific Assumptions	12
3.2.1	Bayside Power Station	12
3.2.2	Big Bend Power Station	12
3.2.3	Polk Power Station	13
3.2.4	MacDill AFB RICE/Battery Storage	13
3.3	Solar Site Specific Assumptions	13
3.3.1	Agrivoltaics Solar	13
3.3.2	Alafia Solar	13
3.3.3	Balm Solar	13
3.3.4	Big Bend Floating Solar	14
3.3.5	Big Bend Solar	14
3.3.6	Big Bend Solar II	14
3.3.7	Bonnie Mine Solar	14
3.3.8	Brewster Solar	14
3.3.9	Bull Frog Creek Solar	14
3.3.10	Cotton Mouth Ranch Solar	15
3.3.11	Durrance Solar	15
3.3.12	Eastern PVS+ES Solar	15
3.3.13	English Creek Solar	15
3.3.14	Florida Aquarium Pavilion Solar	15
3.3.15	Future Solar Site I	15
3.3.16	Future Solar Site II	16
3.3.17	Grange Hall Solar	16
3.3.18	Jamison Solar	16
3.3.19	Juniper Solar	16
3.3.20	Lake Hancock Solar	16
3.3.21	Lake Mabel	16
3.3.22	Laurel Oaks Solar	17
3.3.23	Legoland Solar	17
3.3.24	Lithia Solar	17
3.3.25	Little Manatee River	17
3.3.26	Magnolia Solar	17
3.3.27	Mountain View Solar	17
3.3.28	Payne Creek Solar	18
3.3.29	Peace Creek Solar	18
3.3.30	Riverside Solar	18
3.3.31	Tampa International Solar	18
3.3.32	Wimauma Solar	18

4.0 Results

19

**TABLES**

---

Table 1-1:	Decommissioning Cost Summary (2023\$)	i
Table 1-1:	Site Visit Dates	2
Table 3-1:	2023 Scrap Pricing	11
Table 3-2:	2023 Additional Scrap Pricing	12
Table 4-1:	Decommissioning Cost Summary (2023\$)	19

## LIST OF ABBREVIATIONS

---

### Abbreviation

1898 & Co.

BESS

BOP

C&D

CT

Client

GSU

HDPE

HRSG

IGCC

MW

MW-AC

PCBs

Plants

RICE

ST

Study

TECO

### Term/Phrase/Name

1898 & Co., a division of Burns & McDonnell Engineering Company, Inc.

Battery Energy Storage System

Balance of Plant

Construction and Demolition

Combustion Turbine

TECO

Generator Step Up

High Density Polyethylene

Heat Recovery Steam Generators

Integrated Gasification Combined Cycle

Megawatts

Megawatts Alternating Current

Polychlorinated Biphenyls

Power Generation Assets

Reciprocating Internal Combustion Engine

Steam Turbine

Decommissioning Cost Study

Tampa Electric Company



## Executive Summary

Tampa Electric Company (“TECO”) retained 1898 & Co., a division of Burns & McDonnell Engineering Company, Inc. (hereinafter called “1898 & Co.”), to conduct a Decommissioning Cost Study (“Study”) for power generation assets (“Plants”) in Florida. The assets include natural gas-fired, coal-fired, battery storage, and solar generating facilities. The purpose of the Study was to review the facilities and to make a recommendation to TECO regarding the total cost to decommission the facilities at the end of their useful lives. The decommissioning costs were developed by 1898 & Co. using information provided by TECO and in-house data available to 1898 & Co.

1898 & Co. has prepared cost estimates in 2023 dollars for the decommissioning of the Plants. These cost estimates are summarized in Table 1-1. When TECO determines that the Plants should be retired, the above grade equipment and steel structures are assumed to have sufficient scrap value to a scrap contractor to offset a portion of the decommissioning costs. TECO will incur costs in the demolition and restoration of the sites less the scrap value of equipment and bulk recycled metals.

Table 1-1: Decommissioning Cost Summary (2023\$)

Plant	Decommissioning Costs	Salvage Credits	Net Project Cost
Agrivoltaics Solar	\$ 126,600	\$ (38,800)	\$ 87,800
Balm Solar	\$ 18,112,100	\$ (7,390,700)	\$ 10,721,400
Bayside	\$ 33,045,000	\$ (16,583,000)	\$ 16,462,000
Big Bend	\$ 86,850,000	\$ (13,018,000)	\$ 73,832,000
Big Bend Floating Solar	\$ 99,500	\$ (76,100)	\$ 23,400
Big Bend Solar	\$ 4,321,300	\$ (969,700)	\$ 3,351,600
Big Bend Solar Phase 2	\$ 1,605,200	\$ (537,900)	\$ 1,067,300
Bonnie Mine Solar	\$ 7,265,000	\$ (2,211,400)	\$ 5,053,600
Durrance Solar	\$ 12,169,000	\$ (4,340,200)	\$ 7,828,800
Eastern PVS+ES Solar	\$ 105,300	\$ (33,700)	\$ 71,600
Florida Aquarium Pavilion	\$ 12,700	\$ (5,000)	\$ 7,700
Grange Hall Solar	\$ 11,086,100	\$ (3,628,000)	\$ 7,458,100
Jamison Solar	\$ 11,175,600	\$ (3,500,400)	\$ 7,675,200
Lake Hancock Solar	\$ 8,761,000	\$ (2,889,500)	\$ 5,871,500
Laurel Oaks Solar	\$ 8,305,900	\$ (2,217,600)	\$ 6,088,300
Legoland Solar	\$ 172,100	\$ (31,100)	\$ 141,000
Lithia Solar	\$ 13,536,500	\$ (4,272,200)	\$ 9,264,300
Little Manatee River	\$ 14,167,400	\$ (4,602,400)	\$ 9,565,000
MacDill AFB RICE/Battery	\$ 2,025,000	\$ (1,267,000)	\$ 758,000



Magnolia Solar	\$ 12,151,300	\$ (2,631,500)	\$ 9,519,800
Mountain View Solar	\$ 7,202,000	\$ (1,793,600)	\$ 5,408,400
Payne Creek Solar	\$ 13,470,500	\$ (4,240,600)	\$ 9,229,900
Peace Creek Solar	\$ 9,713,400	\$ (3,300,700)	\$ 6,412,700
Polk	\$ 29,552,000	\$ (13,869,000)	\$ 15,683,000
Riverside Solar	\$ 8,768,800	\$ (2,092,100)	\$ 6,676,700
Tampa International Solar	\$ 815,900	\$ (296,100)	\$ 519,800
Wimauma Solar	\$ 15,414,100	\$ (4,267,300)	\$ 11,146,800
Future Solar Sites			
Plant	Decommissioning Costs	Salvage Credits	Net Project Cost
Alafia Solar	\$ 8,750,200	\$ (2,115,700)	\$ 6,634,500
Brewster Solar	\$ 5,594,500	\$ (1,591,800)	\$ 4,002,700
Bull Frog Creek Solar	\$ 10,077,000	\$ (2,567,900)	\$ 7,509,100
Cotton Mouth Ranch Solar	\$ 10,408,100	\$ (2,550,600)	\$ 7,857,500
English Creek Solar	\$ 9,424,300	\$ (2,546,600)	\$ 6,877,700
Future Solar Site I	\$ 10,501,600	\$ (2,367,300)	\$ 8,134,300
Future Solar Site II	\$ 10,501,600	\$ (2,367,300)	\$ 8,134,300
Juniper Solar	\$ 10,828,400	\$ (2,332,300)	\$ 8,496,100
Lake Mabel	\$ 11,269,900	\$ (3,121,600)	\$ 8,148,300
<b>TOTAL DECOMMISSIONING COST</b>	<b>\$ 417,384,900</b>	<b>\$ (121,664,700)</b>	<b>\$ 295,720,200</b>

The total net project costs presented above include the costs to return the sites to an industrial condition suitable for reuse for development as an industrial facility. Included are the costs to dismantle all power generating equipment and balance of plant (“BOP”) facilities and, where applicable, to perform environmental site restoration activities. Contingency and owner’s indirect costs have been excluded from the cost estimates as requested by TECO. However, it is 1898 & Co.’s typical practice and recommendation that 20 percent contingency be included on the direct costs in the estimates prepared as part of this study and that owner indirect costs be included as 5 percent of the direct costs.

# 1.0 Introduction

## 1.1 Background

1898 & Co. was retained by TECO to conduct a Study for Plants in Florida to estimate the decommissioning costs. The assets include natural gas-fired, coal-fired, battery storage, and solar generating facilities. The purpose of the Study was to review the facilities and to make a recommendation to TECO regarding the total cost to decommission and dismantle the facilities at the end of their useful lives. Individuals from 1898 & Co. visited a representative portion of the Plants evaluated within the Study in August of 2023.

1898 & Co. has prepared over three hundred decommissioning studies on various types of fossil fuel and renewable power plants. In addition to preparing decommissioning cost estimates, 1898 & Co. has supported demolition projects as the owner's engineer. In this capacity, 1898 & Co. has evaluated demolition bids and overseen demolition activities. This has provided 1898 & Co. with insight into a broad range of competitive demolition bids, which also assists in confirming the validity of the decommissioning and dismantling estimates developed by 1898 & Co.

## 1.2 Methodology

The site decommissioning costs were developed using information provided by TECO and in-house data 1898 & Co. has collected from previous project experience. 1898 & Co. estimated quantities for equipment based on a visual inspection of the facilities, reviews of engineering drawings, an in-house database of plant equipment quantities, and professional judgement. For each Plant, quantities were estimated for each required task. Current market pricing for labor rates and equipment was then developed for each task. The unit pricing was developed for each site based on labor rates, equipment costs, and disposal costs specific to the area in which the work is to be performed. These rates were applied to the quantities for the Plants to determine the total cost of decommissioning and dismantling.

The decommissioning costs include the cost to return the site to an industrial condition, suitable for reuse for development of an industrial facility. Included are the costs to decommission and dismantle all the assets owned by TECO at the sites, including power generating equipment and Balance of Plant facilities.

## 1.3 Site Visit

Representatives from 1898 & Co. and TECO visited the sites in August of 2023. A representative portion of the sites was visited. The site visits consisted of a tour of each facility listed below, with Plant personnel, to review the equipment installed at each site.



Table 1-1: Site Visit Dates

Plant	Site Visit Day
Big Bend Power Station	August 22, 2023
Big Bend Solar	August 22, 2023
Big Bend Floating Solar	August 22, 2023
Agrivoltaics	August 22, 2023
Florida Aquarium Pavilion Solar	August 23, 2023
Bayside Power Station	August 23, 2023
Eastern PVS+ES Solar	August 23, 2023
Magnolia Solar	August 23, 2023

Mr. Kevin Payne, from TECO, served as the representative throughout the site visits. The following 1898 & Co. representatives comprised the site team:

1. Mr. Carl Turner, Project Manager
2. Mr. Stephen Henson, Project Engineer
3. Ms. Abby Yi, Lead Project Analyst
4. Mr. Marco Barajas, Project Analyst

## 2.0 Plant Descriptions

The following sections provide site descriptions for each of the power plants included in this Study.

### 2.1 Agrivoltaics

Agrivoltaics is a solar farm located in Apollo Beach, Florida. The solar farm reached commercial operation June 2022 and has a total capacity of 1 Megawatt Alternating Current (“MW-AC”). The solar site has 2,688 photovoltaic solar panels and are arranged in 9 fixed-tilt tables in a 70x4 configuration and 1 fixed-tilt table in a 42x4 that provide partial shade to crops growing beneath.

### 2.2 Alafia Solar

Alafia is a future solar farm. The solar farm is expected to reach commercial operation in December 2023 and has a total planned capacity of 60 MW-AC.

### 2.3 Balm Solar

Balm Solar is a solar farm located in Hillsborough County, Florida. The solar farm reached commercial operation September 2018 and has a total capacity of 74.4 MW-AC. The solar site has 719,100 photovoltaic solar panels in a 60x3 configuration on fixed-tilt tables.

### 2.4 Bayside Power Station

Bayside is located just north of Gibsonton, Florida on Port Sutton Road near Tampa Bay. The plant consists of two combined cycle gas turbine powerblocks and four simple cycle units. The facility consists of seven GE 7FA CTs, with associated Heat Recovery Steam Generators (“HRSG”). Three of the combustion turbines (“CT”) and HRSG sets, Bayside 1A, 1B, 1C, were utilized to repower the steam turbine (“ST”) from Gannon Unit 5 and came online in 2003. Bayside CT and HRSG sets 2A, 2B, 2C, and 2D came online in 2004, repowering the steam turbine from Gannon Unit 6. The facility also includes four Pratt & Whitney TwinPac Units. The remaining facilities at the site, including the common administrative, warehouse, maintenance buildings, water storage tanks, and ponds, are all now considered part of the Bayside Power Station, since the Gannon Power Station has been taken out of service. Additionally, the steam turbines from Gannon Unit 5 and Gannon Unit 6 are now considered part of the Bayside facility along with the entire steam turbine building now that these steam turbine units have been repowered as part of the Bayside Power Station. New traveling screens and an organism return system are in the process of being installed at Bayside and are included in the Study.

### 2.5 Big Bend Power Station

Big Bend is a coal fired power plant located north of Apollo Beach, Florida and is surrounded by a seawall. The site is roughly 1,500 acres and after its 2022 modernization has a generating capacity of more than 2,000 megawatts (“MW”). The first coal unit came online in 1970, followed by Unit 2 in 1973, Unit 3 in 1976, and Unit 4 in 1985. As part of the modernization project, Unit 1 steam turbine was repowered for combined cycle operation with two (2) GE 7HA.02 combined cycle combustion turbines. In 2009, a 60 MW Pratt & Whitney TwinPac Natural gas peaking unit was added to the plant. Unit 2 was retired in 2022 and Unit 3 was retired in 2023. Unit 4 remains in operation with coal or natural gas. Unit 4 includes selective catalytic reduction systems, air quality control systems, electrostatic precipitators, and flue gas desulfurizers. A barge unloading facility for coal and a limestone unloading handling and storage area are both located on-site. There are several ponds on the premises, including bottom ash ponds and storm water settling ponds, along with slag handling and gypsum handling and storage locations.

## 2.6 Big Bend Floating Solar

Big Bend Floating Solar is a solar farm located in Apollo Beach, Florida in an ash pond at the Big Bend Power Station. The solar farm reached commercial operation March 2022 and has a total capacity of 1 MW-AC. The solar site has 3,152 photovoltaic solar panels. The solar site covers approximately 20% of the ash pond and is configured into two groups dependent on the brand of the module. The First Solar module group contains 264 tables in a 6x1 configuration. The Canadian Solar group contains 196 tables in an 8x1 configuration. The inverters at this site are on racks under metal corrugated sheets.

## 2.7 Big Bend Solar

Big Bend solar is a solar farm located in Apollo Beach, Florida near the Big Bend Power Station. The solar farm reached commercial operation February 2017 and has total capacity of 19,800 kW-AC. The solar site has 200,000 photovoltaic solar panels on a single-axis tracking array. The Big Bend solar farm additionally includes batteries for energy storage.

## 2.8 Big Bend Solar II

Big Bend solar is a solar farm located in Apollo Beach, Florida near the Big Bend Power Plant. The solar farm reached commercial operation January 2022 and has total capacity of 45,800 kW-AC. The solar site has 116,000 photovoltaic solar panels on single-axis tracking systems.

## 2.9 Bonnie Mine Solar

Bonnie Mine is a solar farm located in Mulberry, Florida. The solar farm reached commercial operation January 2019 and has a total capacity of 37.5 MW-AC. The solar site has 349,440 photovoltaic solar panels on single-axis tracking systems.

## 2.10 Brewster Solar<sup>1</sup>

Brewster Solar is a future solar project expected to be located in Polk County, Florida. The project has a planned total capacity of 40 MW-AC and is assumed to reach commercial operation in December 2024.

## 2.11 Bull Frog Creek Solar<sup>2</sup>

Bull Frog Creek Solar is a future solar project expected to be located in Hillsborough County, Florida. The project has a planned total capacity of 74.5 MW-AC and is assumed to reach commercial operation in December 2025.

## 2.12 Cotton Mouth Ranch Solar<sup>3</sup>

Cotton Mouth Ranch solar is a future solar project expected to be located in Hillsborough County, Florida. The project has a planned total capacity of 74.5 MW-AC and is assumed to reach commercial operation in December 2025.

---

<sup>1</sup> Future Solar Site. Property location and name subject to change.

<sup>2</sup> Future Solar Site. Property location and name subject to change.

<sup>3</sup> Future Solar Site. Property location and name subject to change.

### 2.13 Durrance Solar

Durrance Solar is a solar farm located in Mulberry, Florida. The solar farm reached commercial operation January 2021 and has a total capacity of 60 MW-AC. The solar site has 585,300 photovoltaic solar panels that are arranged in a 4x15 configuration.

### 2.14 Eastern PVS+ES Solar

Eastern PVS+ES Solar is a solar generating facility located in Tampa, Florida. The solar site has a total capacity of .8625 MW-AC and contains 2,353 photovoltaic solar panels configured into 5 fixed tables that provide partial shade to parking spots below and charging for electric vehicles.

### 2.15 English Creek Solar

English Creek Solar is a solar project located in Tampa, Florida. The solar site has a planned total capacity of 74.5 MW-AC and is assumed to include 193,700 photovoltaic solar panels.

### 2.16 Florida Aquarium Pavilion

Florida Aquarium Pavilion is a solar farm located in Tampa, Florida. The solar farm reached commercial operation June 2021 and has a total capacity of 100 kW-AC. The solar site has 1,140 photovoltaic solar panels arranged on top of the aquarium's pavilion roof.

### 2.17 Future Solar Site I<sup>4</sup>

Future Solar Site I is a future solar site and is expected to reside on 500 acres in Florida. It is planned to reach commercial operation in 2025, with a planned capacity of 74.5 MW-AC.

### 2.18 Future Solar Site II<sup>5</sup>

Future Solar Site II is a future solar site and is expected to reside on 500 acres in Florida. It is planned to reach commercial operation in 2025, with a planned capacity of 74.5 MW-AC.

### 2.19 Grange Hall Solar

Grange Hall is a solar farm located in Wimauma, Florida. The solar farm reached commercial operation in January 2019 and has a total capacity of 61.1 MW-AC. The solar site has 595,260 photovoltaic solar panels that are arranged in 60x3 configuration.

### 2.20 Jamison Solar

Jamison Solar is a solar farm located in Mulberry, Florida. The solar farm reached commercial operation April 2022 and has a total capacity of 74.5 MW-AC. The solar site has 188,226 photovoltaic solar panels that are arranged on single-axis tracking systems.

### 2.21 Juniper Solar

Juniper Solar is a future solar project expected to be located in Crystal Springs, Florida. The solar site has a planned total capacity of 70 MW-AC and is assumed to reach commercial operation in December 2023.

---

<sup>4</sup> Future Solar Site. Property location and name subject to change.

<sup>5</sup> Future Solar Site. Property location and name subject to change.

### 2.22 Lake Hancock Solar

Lake Hancock Solar is a solar farm located in Bartow, Florida. The solar farm reached commercial operation May 2019 and has a total capacity of 49.6 MW-AC. The solar site has 467,820 photovoltaic solar panels arranged in a 60x3 configuration on fixed-tilt tables.

### 2.23 Lake Mabel Solar

Lake Mabel Solar is a future solar site expected to be located in Dundee, Florida. The solar site has a planned total capacity of 74.5 MW-AC and is assumed to reach commercial operation in December 2023.

### 2.24 Laurel Oak Solar

Laurel Oak Solar is a solar farm located in Plant City, Florida. The solar farm reached commercial operation December 2022 and has a total capacity of 61.2 MW-AC. The solar site has 160,386 photovoltaic solar panels arranged on a single-axis tracking system.

### 2.25 Legoland Solar

Legoland Solar is a solar farm located on the east side of Lake Eloise in Eloise, Florida. There are twelve rows of solar panels that cover the preferred parking lot at the Winter Haven resort and can provide partial shade to approximately 600 vehicles. The solar farm has a total capacity of 1,398 kW-AC and can produce electricity for roughly 200 houses. The project includes 5,218 solar panels.

### 2.26 Lithia Solar

Lithia Solar is a solar farm located in Lithia, Florida. The solar farm reached commercial operation January 2019 and has a total capacity of 74.5 MW-AC. The solar site has 741,720 photovoltaic solar panels arranged in a 60x4 configuration on fixed tables.

### 2.27 Little Manatee Solar

Little Manatee Solar is a solar farm located in Ruskin, Florida. The solar farm reached commercial operation in February 2020 and has a total capacity of 74.5 MW-AC. The solar site has 732,600 photovoltaic solar panels arranged in a 15x4 configuration on fixed tables.

### 2.28 MacDill AFB RICE/Battery

MacDill Air Force Base Reciprocating Internal Combustion Engine (“RICE”) and Battery Storage is in Tampa, Florida. The plant has not yet reached commercial operation. The plant is planned to have four Wartsila 18V50SG RICE engines, installed in two phases, and a battery energy storage system.

### 2.29 Magnolia Solar

Magnolia Solar is a solar farm located in Plant City, Florida. The solar farm reached commercial operation December 2021 and has a total capacity of 74.9 MW-AC. The solar site has 197,646 photovoltaic solar panels arranged in a 6x1 configuration on single-axis tracking systems.

### 2.30 Mountain View Solar

Mountain View Solar is a solar farm located in Dade City, Florida. The solar farm reached commercial operation April 2022 and has a total capacity of 54.6 MW-AC. The solar site has 142,800 photovoltaic solar panels arranged in a 6x1 configuration on single-axis tracking systems.

### 2.31 Payne Creek Solar

Payne Creek Solar is a solar farm located in Bowling Green, Florida. The solar farm reached commercial operation September 2018 and has a total capacity of 70.3 MW-AC. The solar site has 707,940 photovoltaic solar panels arranged in a 3x60 configuration on single-axis tracking systems.

### 2.32 Peace Creek Solar

Peace Creek Solar is a solar farm located in Bartow, Florida. The solar farm reached commercial operation March 2019 and has a total capacity of 55.4 MW-AC. The solar site has 545,000 photovoltaic solar panels arranged in a 60x3 configuration.

### 2.33 Polk Power Station

Polk is located south of Pine Island on roughly 4,300 acres south of Lakeland, Florida. The site consists of an integrated gasification combined cycle (“IGCC”) plant (Unit 1) and four CTs (CTs 2-5) and one ST. Combustion turbine 2 - 5 and the steam turbine operate in combined cycle mode and are collectively known as “Polk 2.” Unit 1 includes a coal gasifier, a GE 7FA CT, a Vogt HRSG and a GE ST. Unit 1 has dual fuel capabilities and can utilize natural gas or syngas from coal or a petcoke and coal blend. The IGCC went into commercial operation 1996. Polk 2 includes 4 GE 7FA combustion turbines that were originally installed as simple cycle units. CT 2 achieved commercial operation in 2000, CT 3 in 2002, and CTs 4 and 5 in 2007. CT 2 and CT 3 are dual fueled, capable of utilizing natural gas or oil. CTs 2-5 each have a nameplate capacity of 165 MW and the ST has a capacity of 460 MW. The facility includes common administrative, warehouse and maintenance buildings. A water treatment plant and cooling tower was also added as part of the Unit 2 combined cycle conversion project.

### 2.34 Riverside Solar

Riverside Solar is a solar farm located in Ruskin, Florida. The solar farm reached commercial operation December 2022 and has a total capacity of 55 MW-AC. The solar site has 168,464 photovoltaic solar panels arranged in a 6x1 configuration on single-axis tracking systems.

### 2.35 Tampa International Solar (TIA)

Tampa International Solar is a solar farm located at Tampa International Airport. The panels are positioned on top of the South Economy Parking Garage and can provide partial shade to approximately 800 vehicles. The project has a total capacity of 2,000 kW-AC. The rooftop array consists of 6,175 panels and covers 175,000 feet.

### 2.36 Wimauma Solar

Wimauma Solar is a solar farm located in Wimauma, Florida. The solar farm reached commercial operation April 2020 and has a total capacity of 74.8 MW-AC. The solar site has 732,420 photovoltaic solar panels arranged in tables of 78x3.

## 3.0 Decommissioning Costs

1898 & Co. has prepared decommissioning cost estimates for the Plants. When TECO determines that each site should be retired, the above grade equipment and steel structures are assumed to have scrap value to a scrap contractor which will offset a portion of the site decommissioning costs. However, TECO will incur costs of dismantling the Plants and restoration of the sites to the extent that those costs exceed the scrap value of equipment and bulk steel.

The decommissioning costs for each site include the cost to return each site to an industrial condition, suitable for reuse for development of an industrial facility. Included are the costs to dismantle all the assets at the sites, including power generating equipment and BOP facilities, as well as the costs to perform environmental site restoration activities.

For purposes of this study, 1898 & Co. assumed that each site will be dismantled as a single project, allowing the most cost-effective demolition methods to be utilized. A summary of several of the means and methods that could be employed is provided in the following paragraphs; however, means and methods will not be dictated to the contractor by 1898 & Co. It will be the contractor's responsibility to determine means and methods that result in safely dismantling the Plants at the lowest possible cost.

Asbestos remediation, as required, would take place prior to commencement of any other demolition activities. Abatement would need to be performed in compliance with all state and federal regulations, including, but not limited to, requirements for sealing off work areas and maintaining negative pressure throughout the removal process. Final clearances and approvals would need to be achieved prior to performing further demolition activities.

High grade assets would then be removed from the site to the extent possible. This would include items such as transformers, transformer coils, circuit breakers, electrical wire, condenser plates and tubes, and heater tubes. High grade assets include precious alloys such as copper, aluminum-brass tubes, stainless steel tubes, and other high value metals occurring in plant systems. High grade asset removal would occur up-front in the schedule, to reduce the potential for theft, to increase cash flow, and for separation of recyclable materials to increase scrap recovery. Methods of removal vary with the location and nature of the asset. Small transformers, small equipment, and wire would likely be removed and shipped as-is for processing at a scrap yard. Large transformers, CT, ST generators, and condensers would likely require some on-site disassembly prior to being shipped to a scrap yard.

Construction and Demolition ("C&D") waste includes items such as non-asbestos insulation, roofing, wood, drywall, plastics, and other non-metallic materials. C&D waste would typically be segregated from scrap and concrete to avoid cross-contamination of waste streams or recycle streams. C&D demolition crews could remove these materials with equipment such as excavators equipped with material handling attachments, skid steers, etc. This material would be consolidated and loaded into bulk containers for disposal.

In general, boilers and Heat Recovery Steam Generators could be felled and cut into manageable sized pieces on the ground. First the structures around the boilers would need to be removed using excavators equipped with shears and grapples. Stairs, grating, elevators, and other high structures would be removed using an "ultra-high reach" excavator, equipped with shears. Following removal of these structures, the boilers or HRSGs would be felled, using explosive blasts. The boilers would then be dismantled using equipment such as excavators equipped with shears and grapples, and the scrap metal loaded onto trailers for recycling.

After the surrounding structures and ductwork have been removed, the stacks would be imploded, using controlled blasts. Following implosion, the stack liners and concrete would be reduced in size to allow for handling and removal.

BOP structures and foundations would likely be demolished using excavators equipped with hydraulic shears, hydraulic grapples, and impact breakers, along with workers utilizing open flame cutting torches. Steel components would be separated, reduced in size, and loaded onto trailers for recycling. Concrete would be broken into manageable sized pieces and stockpiled for crushing on site. Concrete pieces would ultimately be loaded in a hopper and fed through a crusher to be sized for on-site disposal.

### 3.1 General Assumptions Applicable to All Sites

The Following assumptions are made as the basis of all cost estimates.

1. The estimates are inclusive of all costs necessary to properly demolish all structures, equipment, boilers, tanks, conveying and ancillary buildings, and any other associated equipment and buildings to grade level. For the purposes of this Study and the included cost estimates, the sites will be restored to a condition suitable for industrial use.
2. Pricing for all estimates is in 2023 dollars.
3. For purposes of this Study, it is assumed that all units at the power station will be dismantled as part of a single demolition project.
4. Units will be decommissioned to zero generating output. Existing utilities will remain in place for use by the contractor for the duration of the demolition activities.
5. All work will take place in the most cost-efficient method.
6. Labor costs are based on non-Union labor rates for a 40-hour workweek.
7. Soil testing and any other on-site testing has not been conducted for this Study. Any environmental clean-up or removal costs are based on previous testing or assumed levels of contamination.
8. The only environmental costs that are included to address cleanup of contaminated soils, hazardous materials, or other conditions present on-site having a negative environmental impact, are specifically listed under assumptions. No allowances are included for unforeseen environmental remediation activities.
9. TECO will remove or consume all fuel oil and chemicals to the reasonable extent possible prior to commencement of demolition activities. Costs for these activities are not included in the estimate. Costs are included in the estimates for cleaning and flushing fuel oil tanks and lines. Costs have also been included to remove one foot of soil directly below each of the fuel oil tanks to account for the potential for this soil to be contaminated during normal operations.
10. Soil around the generator step-up (“GSU”) transformers and other large transformers will be excavated to a depth of three feet and transported off-site for disposal. It is assumed that the polychlorinated biphenyl (“PCB”) concentrations are below 50 ppm and will not be required to be disposed in a Toxic Substances and Control Act permitted landfill.
11. All burnable coal will be consumed by the plant prior to commencing decommissioning activities. TECO will remove fuel oil, limestone piles, and chemicals prior to commencement of demolition activities. The area underneath the coal piles will be excavated to a depth of two feet below grade to remove any residual coal. This coal soil mix will be disposed of offsite, and this area will be covered with eighteen inches of soil and six inches of topsoil.
12. Costs are included in the estimates for draining and disposing of transformer oils.
13. Hazardous material abatement is included for asbestos and mercury. Lead paint coated materials will be handled by trained personnel as necessary but will not be removed prior to demolition.
14. In general, abatement of asbestos will precede any other work. After final air quality clearances have been reached, demolition can proceed. However, some abatement, including the removal of non-friable gaskets and packings will commence in conjunction with the demolition. If asbestos containing materials are found within the interior of boilers, stacks, ductwork or other equipment (including refractory), abatement will be coordinated closely with demolition.



15. All demolition and abatement activities, including removal of asbestos, will be done in accordance with all applicable Federal, State and Local laws, rules, and regulations.
16. Transmission switchyards and substations within the boundaries of the plant are not part of the demolition scope, unless otherwise noted herein. For purposes of this Study, the division between generation assets and transmission assets is at the high side of the generator step-up transformers. Costs are included for removal of generation leads from the disconnect at the switchyard connection back to the GSU transformers and for the reserve power leads from the switchyard to the reserve power transformers.
17. Step-up transformers, auxiliary transformers, and spare transformers are included for demolition and scrap.
18. All above-grade structures will be demolished. All below-grade structures, including foundations, will be removed to three feet below existing grade, unless otherwise noted in the site-specific assumptions.
19. Foundations greater than three feet below grade will be abandoned in place.
20. Underground structures with cavities will be permanently sealed three feet below grade. Examples include cable tunnels and vaults, coal reclaim conveyor tunnels, and rotary car dumper structures.
21. Cooling towers and basin walls will be removed, and the basin floors will be broken to allow for drainage and then backfilled with on-site soil.
22. Major equipment, structural steel, turbines, generators, transformers, electrical equipment, cabling, wiring, pump skids, above ground piping, and equipment enclosures for the above equipment are sold for scrap and removed from the site by the demolition contractor.
23. To the extent possible, concrete will be crushed and disposed of on-site. All other material that is not sold as scrap will be disposed of at an off-site landfill.
24. Except for the circulating water systems, underground piping will be capped at each end with concrete and abandoned in place. Concrete circulating water piping will be filled with flowable fill material.
25. Storm sewers, catch basins and ducts will be collapsed to two feet below grade, filled and sealed on the upstream side. Horizontal runs will be abandoned in place after being closed.
26. Ponds will have liners removed and disposed of. Pond berms will be graded, and the ponds will be backfilled with crushed concrete or berm material. Ponds, former spray field areas, and dredging areas will be covered with topsoil, graded, and seeded.
27. All production wells will be closed as per state regulations. Production wells will be filled with grout to approximately five feet below surface grade. The top five feet will be over-drilled and filled with soil backfill to grade on top of the grout. Monitoring wells will remain intact.
28. TECO will remove all rolling stock (rail cars, vehicles, cranes, forklift trucks, etc.) and temporary vehicle fuel tanks prior to commencement of demolition activities. These costs are not included in the Study.
29. TECO will remove any spare parts, tools, inventory, or equipment in the buildings prior to commencement of demolition activities. These costs are not included in the Study.
30. Site areas will be graded to achieve suitable site drainage to natural drainage patterns and seeded but grading will be minimized to the extent possible.
31. Valuation and sale of land and all replacement generation costs are excluded from this scope.
32. For purposes of this Study, it is assumed that none of the equipment will have a salvage value in excess of the scrap value of the materials in the equipment at the time of decommissioning. The decommissioning cost estimate is based on the end of useful life of the facility. All equipment, steel, copper, and other metals will be sold as scrap. Credits for salvage value are based on scrap value alone. Resale of equipment and materials is not included.
33. Contingency and owner's indirect costs have been excluded from the cost estimates under direction from TECO. Typically, 1898 & Co. would recommend and include a 20 percent contingency on the direct costs in the estimates and 5 percent owner's indirect costs on the direct costs.
34. Market conditions may result in cost variations at the time of contract execution.

35. Scrap values used in the decommissioning estimates will be provided for each site according to the most recent 12-month average of American Metal Market prices inclusive of the cost to haul the scrap via truck and/or rail to the major market which provides the best price.

Table 3-1: 2023 Scrap Pricing

Plant	Scrap Market Location	Steel Scrap Value (\$/net ton)	Copper Scrap Value (\$/pound)	Aluminum Scrap Value (\$/pound)	Brass Scrap Value (\$/pound)
Agrivoltaics Solar	Cincinnati	\$ (229.38)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Alafia Solar	Cincinnati	\$ (232.53)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Balm Solar	Cincinnati	\$ (227.63)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Bayside Power Station	Cincinnati	\$ (231.83)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Big Bend Power Station	Cincinnati	\$ (229.38)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Big Bend Floating Solar	Cincinnati	\$ (230.08)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Big Bend Solar	Cincinnati	\$ (229.38)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Big Bend Solar Phase 2	Cincinnati	\$ (229.38)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Bonnie Mine Solar	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Brewster Solar	Cincinnati	\$ (221.68)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Bull Frog Creek Solar	Cincinnati	\$ (222.38)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Cotton Mouth Ranch Solar	Cincinnati	\$ (220.63)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Durrance Solar	Cincinnati	\$ (231.13)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Eastern PVS+ES Solar	Cincinnati	\$ (233.58)	\$ (2.81)	\$ (0.35)	\$ (2.22)
English Creek Solar	Cincinnati	\$ (233.23)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Florida Aquarium Pavilion	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Future Solar Site I	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Future Solar Site II	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Grange Hall Solar	Cincinnati	\$ (231.13)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Jamison Solar	Cincinnati	\$ (231.48)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Juniper Solar	Cincinnati	\$ (226.58)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Lake Hancock Solar	Cincinnati	\$ (233.58)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Lake Mabel	Cincinnati	\$ (289.85)	\$ (2.83)	\$ (0.38)	\$ (2.25)
Laurel Oaks Solar	Cincinnati	\$ (232.53)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Legoland Solar	Cincinnati	\$ (289.85)	\$ (2.83)	\$ (0.35)	\$ (2.25)
Lithia Solar	Cincinnati	\$ (225.88)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Little Manatee River	Cincinnati	\$ (225.88)	\$ (2.80)	\$ (0.35)	\$ (2.21)
MacDill AFB RICE/Battery	Cincinnati	\$ (230.43)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Magnolia Solar	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Mountain View Solar	Cincinnati	\$ (221.68)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Payne Creek Solar	Cincinnati	\$ (227.63)	\$ (2.80)	\$ (0.35)	\$ (2.21)
Peace Creek Solar	Cincinnati	\$ (233.58)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Polk Power Station	Cincinnati	\$ (230.08)	\$ (2.80)	\$ (0.35)	\$ (2.22)
Riverside Solar	Cincinnati	\$ (226.58)	\$ (2.80)	\$ (0.35)	\$ (2.21)

Tampa International Solar	Cincinnati	\$ (232.88)	\$ (2.81)	\$ (0.35)	\$ (2.22)
Wimauma Solar	Cincinnati	\$ (231.13)	\$ (2.81)	\$ (0.35)	\$ (2.22)

Table 3-2: 2023 Additional Scrap Pricing

Plant	Scrap Market Location	Stainless Steel Scrap Value (\$/net ton)	Titanium Scrap Value (\$/pound)	Inconel Scrap Value (\$/pound)
Bayside Power Station	Cincinnati	\$ (1,072.93)	\$ (0.32)	\$ (4.51)
Big Bend Power Station	Cincinnati	\$ (1,070.48)	\$ (0.32)	\$ (4.50)
Polk Power Station	Cincinnati	\$ (1,071.18)	\$ (0.30)	\$ (4.50)

### 3.2 Site Specific Assumptions

The following assumptions are in addition to the general assumptions provided above and served as the basis of evaluation for each of the generating facilities for which site-specific decommissioning cost estimates will be developed.

#### 3.2.1 Bayside Power Station

1. It has been assumed that no contamination is present in the abandoned spray areas. No remediation costs have been included for these areas.
2. Asbestos abatement has already occurred as part of the Gannon decommissioning project and the turbine building transite paneling was replaced with steel.
3. Bayside fuel oil tanks have been removed and it is assumed that there is no soil contamination present, therefore fuel oil tank removal and soil remediation has been excluded from the estimate.
4. New traveling screens and an organism return system are being installed at the site, and would be new since the time of the prior Study. Costs for removal of these items are included in the cost estimate.
5. Condenser tubes are comprised of titanium.

#### 3.2.2 Big Bend Power Station

1. The coal unloading facility across Wyandotte Road is included in the estimate and it is assumed that the rail loop will also be removed.
2. It is assumed that approximately 145,800 tons of gypsum will be removed from site and disposed of as part of the gypsum storage remediation cost.
3. The bottom ash ponds, settling pond, south recycle pond, and north recycle pond will have all material removed by TECO prior to decommissioning. As such the costs for removal of this material are not included. The berms will then be graded into the ponds and the area seeded. Costs for these closure activities are included in the estimate.
4. The bottom ash storage pond, former spray field areas, stormwater ponds, and dredging spoil areas will be capped with 24 inches of soil and seeded.
5. The slag storage pond will be capped in place with a High Density Polyethylene (“HDPE”) liner over six inches of fill soil. The HDPE cap will be covered by 24 inches of topsoil and seeded.
6. Circulating water intake and discharge canals will be left as-is, except for the free-standing thermal dilution sheet pile barrier along the discharge canal, which will be removed.
7. Stack removal for Unit 4 is included in the Study. It is assumed that the stack has a brick liner and there is a 4-foot difference in diameter between the stack and the liner.
8. The stack will be felled to the east as one of the last demolition activities on site using implosions. Barriers will be set in place to prevent debris from entering the surrounding canals and wetlands.
9. Condenser tubes are titanium.
10. Estimates for asbestos abatement are based on the prior remaining asbestos volume estimates provided by TECO.

11. Units 2 and 3 have been retired. Any costs associated with Units 2 and 3 are not included in the cost estimate under direction from TECO.
12. Due to the Big Bend Modernization project, it is assumed most of the Unit 1 equipment has been retired except for the steam turbine, steam turbine building, and GSU. Cost to remove the boiler, precipitators, SCR, Scrubber/FGD, cooling water intakes, and circulating water pumps are not included.
13. Unit 1 asbestos was assumed to be partially remediated during the Big Bend Modernization, after discussion during the site visit.

### 3.2.3 Polk Power Station

1. Cooling water recirculation ponds will be left in place as is.
2. The storm water pond located on the north side will be left in place as-is.
3. Scrap values include 433,000 lbs of Inconel from the Syngas Cooler.
4. The slag storage area will be closed with a cap constructed of a High-Density Polyethylene liner over 6 inches of soil. The HDPE liner will be covered by 24-inches of topsoil and seeded.
5. It is assumed that no asbestos is present at this site.
6. Condenser tubes are comprised of stainless steel.

### 3.2.4 MacDill AFB RICE/Battery Storage

1. The cost to remove the piping to the metering and regulation stations is not included in the estimate.
2. Costs to remove RICE Units 1 and 2 as well as future RICE Units 3 and 4 are included in the estimate.
3. Manufacturing information of the battery energy storage system was not available for review. Battery specifications and quantities were assumed based on 1898 & Co. experience.
4. A Lease Agreement was not provided for review including removal requirements. As such, a removal depth of 3 feet below grade was assumed.
5. The battery disposal fees are assumed to be at the expense of the Project. Costs are included for transporting the batteries to a recycling facility.
6. It is assumed no asbestos or environmental contamination is present at the site.

## 3.3 Solar Site Specific Assumptions

### 3.3.1 Agrivoltaics Solar

1. Agrivoltaics Solar is on land owned by TECO. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

### 3.3.2 Alafia Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. The cost for substation removal was not included.

### 3.3.3 Balm Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.

3. The cost for substation removal was not included.

#### 3.3.4 Big Bend Floating Solar

1. Big Bend Floating Solar sits on Big Bend power station's bottom ash storage pond. Remediation cost for the bottom ash storage pond is included in the Big Bend Power Station estimate not in the Big Bend Floating Solar estimate.
2. The cost for substation removal was not included.

#### 3.3.5 Big Bend Solar

1. Big Bend Solar is on land owned by TECO. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Manufacturing information of the battery energy storage system was not available for review. Battery specifications and quantities were assumed based on 1898 & Co. experience.
4. The battery disposal fees are assumed to be at the expense of the Project. Costs are included for transporting the batteries to a recycling facility.
5. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.6 Big Bend Solar II

1. Big Bend Solar II is on land owned by TECO. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.7 Bonnie Mine Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

#### 3.3.8 Brewster Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
4. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
5. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.9 Bull Frog Creek Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. The cost for substation removal was not included.

### 3.3.10 Cotton Mouth Ranch Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.11 Durrance Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.12 Eastern PVS+ES Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

### 3.3.13 English Creek Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.14 Florida Aquarium Pavilion Solar

1. Florida Aquarium Pavilion Solar is a rooftop solar site. It is assumed 15 percent of the rooftop under the panels will require restoration after decommissioning.
2. The cost for substation removal was not included.

### 3.3.15 Future Solar Site I

1. Because the location of Future Solar Site I has not yet been determined, an SCI of 100 percent was applied.
1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.16 Future Solar Site II

5. Because the location of Future Solar Site II has not yet been determined, an SCI of 100 percent was applied.
6. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
7. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
8. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
9. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.17 Grange Hall Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

### 3.3.18 Jamison Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.19 Juniper Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.
4. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

### 3.3.20 Lake Hancock Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

### 3.3.21 Lake Mabel

4. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
5. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
6. Drawings were not provided for review; project quantities and specifications were assumed based on other TECO solar projects and 1898 & Co. experience.

7. Manufacturing information of the battery energy storage system was not available for review. Battery specifications and quantities were assumed based on 1898 & Co. experience.
8. The battery disposal fees are assumed to be at the expense of the Project. Costs are included for transporting the batteries to a recycling facility.
9. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.22 Laurel Oaks Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.23 Legoland Solar

1. Legoland Solar is on land owned by Legoland. All materials and support systems will be removed to grade.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.24 Lithia Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

#### 3.3.25 Little Manatee River

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

#### 3.3.26 Magnolia Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.27 Mountain View Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.



3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.28 Payne Creek Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

#### 3.3.29 Peace Creek Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. The cost for substation removal was not included.

#### 3.3.30 Riverside Solar

1. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
2. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
3. Substations of the solar sites will be partially demolished. Costs are included for removal of the MV breakers, associated structures, and main power transformer.

#### 3.3.31 Tampa International Solar

1. It is assumed that all concrete support systems will be removed to the floor elevation of the rooftop parking structure on which they sit.
2. Approximately 15 percent of the rooftop was assumed to require restoration following decommissioning.
3. The cost for substation removal was not included.

#### 3.3.32 Wimauma Solar

4. A solar lease agreement was not available for review. A removal depth of 3 feet below grade was assumed.
5. The area inside the perimeter fencing is assumed to be disturbed and requires grading and reseeding as part of decommissioning.
6. New battery energy storage system layouts were provided by TECO. Manufacturing information of the battery energy storage system was not available for review. Battery specifications and quantities were assumed based on 1898 & Co. experience.
7. The battery disposal fees are assumed to be at the expense of the Project. Costs are included for transporting the batteries to a recycling facility.
8. The cost for substation removal was not included.

## 4.0 Results

1898 & Co. has prepared cost estimates in 2023 dollars for the decommissioning of the Plants. These costs are summarized in the following table. When TECO determines that the Plants should be retired, the above grade equipment and steel structures are assumed to have sufficient scrap value to a scrap contractor to offset a portion of the decommissioning costs. TECO will incur costs in the demolition and restoration of the sites less the salvage value of equipment and bulk recycled metals.

Table 4-1: Decommissioning Cost Summary (2023\$)

Plant	Decommissioning Costs	Salvage Credits	Net Project Cost
Agrivoltaics Solar	\$ 126,600	\$ (38,800)	\$ 87,800
Balm Solar	\$ 18,112,100	\$ (7,390,700)	\$ 10,721,400
Bayside	\$ 33,045,000	\$ (16,583,000)	\$ 16,462,000
Big Bend	\$ 86,850,000	\$ (13,018,000)	\$ 73,832,000
Big Bend Floating Solar	\$ 99,500	\$ (76,100)	\$ 23,400
Big Bend Solar	\$ 4,321,300	\$ (969,700)	\$ 3,351,600
Big Bend Solar Phase 2	\$ 1,605,200	\$ (537,900)	\$ 1,067,300
Bonnie Mine Solar	\$ 7,265,000	\$ (2,211,400)	\$ 5,053,600
Durrance Solar	\$ 12,169,000	\$ (4,340,200)	\$ 7,828,800
Eastern PVS+ES Solar	\$ 105,300	\$ (33,700)	\$ 71,600
Florida Aquarium Pavilion	\$ 12,700	\$ (5,000)	\$ 7,700
Grange Hall Solar	\$ 11,086,100	\$ (3,628,000)	\$ 7,458,100
Jamison Solar	\$ 11,175,600	\$ (3,500,400)	\$ 7,675,200
Lake Hancock Solar	\$ 8,761,000	\$ (2,889,500)	\$ 5,871,500
Laurel Oaks Solar	\$ 8,305,900	\$ (2,217,600)	\$ 6,088,300
Legoland Solar	\$ 172,100	\$ (31,100)	\$ 141,000
Lithia Solar	\$ 13,536,500	\$ (4,272,200)	\$ 9,264,300
Little Manatee River	\$ 14,167,400	\$ (4,602,400)	\$ 9,565,000
MacDill AFB RICE/Battery	\$ 2,025,000	\$ (1,267,000)	\$ 758,000
Magnolia Solar	\$ 12,151,300	\$ (2,631,500)	\$ 9,519,800
Mountain View Solar	\$ 7,202,000	\$ (1,793,600)	\$ 5,408,400
Payne Creek Solar	\$ 13,470,500	\$ (4,240,600)	\$ 9,229,900
Peace Creek Solar	\$ 9,713,400	\$ (3,300,700)	\$ 6,412,700
Polk	\$ 29,552,000	\$ (13,869,000)	\$ 15,683,000
Riverside Solar	\$ 8,768,800	\$ (2,092,100)	\$ 6,676,700
Tampa International Solar	\$ 815,900	\$ (296,100)	\$ 519,800
Wimauma Solar	\$ 15,414,100	\$ (4,267,300)	\$ 11,146,800

November 20, 2023 | Confidential Information

TECO Decommissioning Cost Estimate Study

Future Solar Sites			
Plant	Decommissioning Costs	Salvage Credits	Net Project Cost
Alafia Solar	\$ 8,750,200	\$ (2,115,700)	\$ 6,634,500
Brewster Solar	\$ 5,594,500	\$ (1,591,800)	\$ 4,002,700
Bull Frog Creek Solar	\$ 10,077,000	\$ (2,567,900)	\$ 7,509,100
Cotton Mouth Ranch Solar	\$ 10,408,100	\$ (2,550,600)	\$ 7,857,500
English Creek Solar	\$ 9,424,300	\$ (2,546,600)	\$ 6,877,700
Future Solar Site I	\$ 10,501,600	\$ (2,367,300)	\$ 8,134,300
Future Solar Site II	\$ 10,501,600	\$ (2,367,300)	\$ 8,134,300
Juniper Solar	\$ 10,828,400	\$ (2,332,300)	\$ 8,496,100
Lake Mabel	\$ 11,269,900	\$ (3,121,600)	\$ 8,148,300
<b>TOTAL DECOMMISSIONING COST</b>	<b>\$ 417,384,900</b>	<b>\$ (121,664,700)</b>	<b>\$ 295,720,200</b>

## APPENDIX A - COST ESTIMATE SUMMARIES

---

**Table A-1**  
**Agrivoltaics Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Agrivoltaics Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 15,500	\$ 16,100	\$ 5,100	\$ -	\$ 36,700	\$ -
Panel Supports/Rack	\$ 23,100	\$ 24,000	\$ -	\$ -	\$ 47,100	\$ -
Electrical & Wiring	\$ 1,000	\$ 1,000	\$ -	\$ -	\$ 2,000	\$ -
Site Restoration	\$ 7,200	\$ 7,500	\$ -	\$ 26,000	\$ 40,700	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 100	\$ -	\$ 100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (38,800)
<b>Subtotal</b>	<b>\$ 46,800</b>	<b>\$ 48,600</b>	<b>\$ 5,200</b>	<b>\$ 26,000</b>	<b>\$ 126,600</b>	<b>\$ (38,800)</b>
<b>Agrivoltaics Solar Subtotal</b>	<b>\$ 46,800</b>	<b>\$ 48,600</b>	<b>\$ 5,200</b>	<b>\$ 26,000</b>	<b>\$ 126,600</b>	<b>\$ (38,800)</b>
TOTAL DECOM COST (CREDIT)					\$ 126,600	\$ (38,800)
PROJECT INDIRECTS (0%)					\$ -	
CONTINGENY (0%)					\$ -	
TOTAL PROJECT COST (CREDIT)					\$ 126,600	\$ (38,800)
TOTAL NET PROJECT COST (CREDIT)					\$ 87,800	

**Table A-2**  
**Alafia Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Alafia Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,261,900	\$ 1,314,500	\$ 437,800	\$ -	\$ 3,014,200	\$ -
Panel Supports/Rack	\$ 1,190,700	\$ 1,240,200	\$ -	\$ -	\$ 2,430,900	\$ -
Electrical & Wiring	\$ 185,200	\$ 192,900	\$ -	\$ -	\$ 378,100	\$ -
Site Restoration	\$ 150,300	\$ 156,500	\$ -	\$ 2,605,600	\$ 2,912,400	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 11,400	\$ -	\$ 11,400	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,115,700)
<b>Subtotal</b>	<b>\$ 2,788,100</b>	<b>\$ 2,904,100</b>	<b>\$ 452,400</b>	<b>\$ 2,605,600</b>	<b>\$ 8,750,200</b>	<b>\$ (2,115,700)</b>
<b>Alafia Solar Subtotal</b>	<b>\$ 2,788,100</b>	<b>\$ 2,904,100</b>	<b>\$ 452,400</b>	<b>\$ 2,605,600</b>	<b>\$ 8,750,200</b>	<b>\$ (2,115,700)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 8,750,200</b>	<b>\$ (2,115,700)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 8,750,200</b>	<b>\$ (2,115,700)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 6,634,500</b>	

**Table A-3**  
**Balm Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Balm Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 2,065,500	\$ 2,151,500	\$ -	\$ -	\$ 4,217,000	\$ -
Panel Supports/Rack	\$ 5,564,300	\$ 5,796,000	\$ -	\$ -	\$ 11,360,300	\$ -
Electrical & Wiring	\$ 119,200	\$ 124,200	\$ -	\$ -	\$ 243,400	\$ -
Site Restoration	\$ 120,600	\$ 125,600	\$ -	\$ 2,032,200	\$ 2,278,400	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 3,900	\$ -	\$ 3,900	\$ -
Debris	\$ -	\$ -	\$ 9,100	\$ -	\$ 9,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (7,390,700)
<b>Subtotal</b>	<b>\$ 7,869,600</b>	<b>\$ 8,197,300</b>	<b>\$ 13,000</b>	<b>\$ 2,032,200</b>	<b>\$ 18,112,100</b>	<b>\$ (7,390,700)</b>
<b>Balm Solar Subtotal</b>	<b>\$ 7,869,600</b>	<b>\$ 8,197,300</b>	<b>\$ 13,000</b>	<b>\$ 2,032,200</b>	<b>\$ 18,112,100</b>	<b>\$ (7,390,700)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 18,112,100</b>	<b>\$ (7,390,700)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 18,112,100</b>	<b>\$ (7,390,700)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 10,721,400</b>	

**Table A-4**  
**Bayside**  
**Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Bayside</b>						
<i>Unit 1</i>						
Aux Boiler	\$ 8,000	\$ 13,000	\$ -	\$ -	\$ 21,000	\$ -
CTGs and HRSGs	\$ 2,264,000	\$ 3,639,000	\$ -	\$ -	\$ 5,903,000	\$ -
Steam Turbine & Building	\$ 1,014,000	\$ 1,630,000	\$ -	\$ -	\$ 2,644,000	\$ -
SCR	\$ 96,000	\$ 155,000	\$ -	\$ -	\$ 251,000	\$ -
Stacks	\$ 107,000	\$ 172,000	\$ -	\$ -	\$ 279,000	\$ -
GSU & Foundation	\$ 140,000	\$ 224,000	\$ -	\$ -	\$ 364,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 54,000	\$ -	\$ 54,000	\$ -
Debris	\$ -	\$ -	\$ 27,000	\$ -	\$ 27,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (6,200,000)
<b>Subtotal</b>	<b>\$ 3,629,000</b>	<b>\$ 5,833,000</b>	<b>\$ 81,000</b>	<b>\$ -</b>	<b>\$ 9,543,000</b>	<b>\$ (6,200,000)</b>
<i>Unit 2</i>						
Aux Boiler	\$ 11,000	\$ 18,000	\$ -	\$ -	\$ 29,000	\$ -
CTGs and HRSGs	\$ 3,230,000	\$ 5,193,000	\$ -	\$ -	\$ 8,423,000	\$ -
Steam Turbine & Building	\$ 1,024,000	\$ 1,646,000	\$ -	\$ -	\$ 2,670,000	\$ -
SCR	\$ 127,000	\$ 204,000	\$ -	\$ -	\$ 331,000	\$ -
Stacks	\$ 142,000	\$ 229,000	\$ -	\$ -	\$ 371,000	\$ -
GSU & Foundation	\$ 178,000	\$ 287,000	\$ -	\$ -	\$ 465,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 54,000	\$ -	\$ 54,000	\$ -
Debris	\$ -	\$ -	\$ 22,000	\$ -	\$ 22,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (7,954,000)
<b>Subtotal</b>	<b>\$ 4,712,000</b>	<b>\$ 7,577,000</b>	<b>\$ 76,000</b>	<b>\$ -</b>	<b>\$ 12,365,000</b>	<b>\$ (7,954,000)</b>
<i>Units 3-6</i>						
CTGs and HRSGs	\$ 648,000	\$ 1,042,000	\$ -	\$ -	\$ 1,690,000	\$ -
Stacks	\$ 21,000	\$ 34,000	\$ -	\$ -	\$ 55,000	\$ -
GSU & Foundation	\$ 19,000	\$ 30,000	\$ -	\$ -	\$ 49,000	\$ -
Debris	\$ -	\$ -	\$ 9,000	\$ -	\$ 9,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (1,837,000)
<b>Subtotal</b>	<b>\$ 688,000</b>	<b>\$ 1,106,000</b>	<b>\$ 9,000</b>	<b>\$ -</b>	<b>\$ 1,803,000</b>	<b>\$ (1,837,000)</b>
<i>Common</i>						
Cooling Water Intakes and Circulating Water Pumps	\$ 80,000	\$ 128,000	\$ -	\$ -	\$ 208,000	\$ -
Roads	\$ 251,000	\$ 403,000	\$ -	\$ -	\$ 654,000	\$ -
All BOP Buildings	\$ 164,000	\$ 263,000	\$ -	\$ -	\$ 427,000	\$ -
Fuel Equipment	\$ 8,000	\$ 12,000	\$ -	\$ -	\$ 20,000	\$ -
All Other Tanks	\$ 994,000	\$ 1,597,000	\$ -	\$ -	\$ 2,591,000	\$ -
Transformers & Foundation	\$ 22,000	\$ 36,000	\$ -	\$ 569,000	\$ 627,000	\$ -
Mercury & Universal Waste Disposal	\$ -	\$ -	\$ -	\$ 36,000	\$ 36,000	\$ -
Pond Closure	\$ -	\$ -	\$ -	\$ 2,627,000	\$ 2,627,000	\$ -
Concrete Removal, Crushing, & Disposal	\$ -	\$ -	\$ 60,000	\$ -	\$ 60,000	\$ -
Grading & Seeding	\$ -	\$ -	\$ -	\$ 2,071,000	\$ 2,071,000	\$ -
Debris	\$ -	\$ -	\$ 13,000	\$ -	\$ 13,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (592,000)
<b>Subtotal</b>	<b>\$ 1,519,000</b>	<b>\$ 2,439,000</b>	<b>\$ 73,000</b>	<b>\$ 5,303,000</b>	<b>\$ 9,334,000</b>	<b>\$ (592,000)</b>
<b>Bayside Subtotal</b>	<b>\$ 10,548,000</b>	<b>\$ 16,955,000</b>	<b>\$ 239,000</b>	<b>\$ 5,303,000</b>	<b>\$ 33,045,000</b>	<b>\$ (16,583,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 33,045,000</b>	<b>\$ (16,583,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					\$ -	\$ -
<b>CONTINGENY (0%)</b>					\$ -	\$ -
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 33,045,000</b>	<b>\$ (16,583,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 16,462,000</b>	



Table A-5  
Big Bend  
Decommissioning Cost Summary

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Big Bend</b>						
<i>Unit 1</i>						
Asbestos Removal	\$ -	\$ -	\$ -	\$ 383,000	\$ 383,000	\$ -
Steam Turbine & Building	\$ 863,000	\$ 1,388,000	\$ -	\$ -	\$ 2,251,000	\$ -
GSU & Foundation	\$ 59,000	\$ 95,000	\$ -	\$ -	\$ 154,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 39,000	\$ -	\$ 39,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (1,571,000)
<b>Subtotal</b>	<b>\$ 922,000</b>	<b>\$ 1,483,000</b>	<b>\$ 39,000</b>	<b>\$ 569,000</b>	<b>\$ 3,013,000</b>	<b>\$ (1,571,000)</b>
<i>Unit 4</i>						
Asbestos Removal	\$ -	\$ -	\$ -	\$ 837,000	\$ 837,000	\$ -
Boiler	\$ 1,595,000	\$ 2,563,000	\$ -	\$ -	\$ 4,158,000	\$ -
Steam Turbine & Building	\$ 891,000	\$ 1,432,000	\$ -	\$ -	\$ 2,323,000	\$ -
Precipitator	\$ 253,000	\$ 407,000	\$ -	\$ -	\$ 660,000	\$ -
SCR	\$ 585,000	\$ 941,000	\$ -	\$ -	\$ 1,526,000	\$ -
Scrubber / FGD	\$ 302,000	\$ 485,000	\$ -	\$ -	\$ 787,000	\$ -
Stacks	\$ 439,000	\$ 705,000	\$ -	\$ -	\$ 1,144,000	\$ -
GSU & Foundation	\$ 60,000	\$ 97,000	\$ -	\$ -	\$ 157,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 132,000	\$ -	\$ 132,000	\$ -
Debris	\$ -	\$ -	\$ 428,000	\$ -	\$ 428,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,283,000)
<b>Subtotal</b>	<b>\$ 4,125,000</b>	<b>\$ 6,630,000</b>	<b>\$ 560,000</b>	<b>\$ 1,002,000</b>	<b>\$ 12,317,000</b>	<b>\$ (4,283,000)</b>
<i>GT 4</i>						
CTGs and HRSGs	\$ 85,000	\$ 137,000	\$ -	\$ -	\$ 222,000	\$ -
Flood Wall	\$ 61,000	\$ 98,000	\$ -	\$ -	\$ 159,000	\$ -
Stacks	\$ 4,000	\$ 6,000	\$ -	\$ -	\$ 10,000	\$ -
GSU & Foundation	\$ 17,000	\$ 27,000	\$ -	\$ -	\$ 44,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 5,000	\$ -	\$ 5,000	\$ -
Debris	\$ -	\$ -	\$ 2,000	\$ -	\$ 2,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (358,000)
<b>Subtotal</b>	<b>\$ 167,000</b>	<b>\$ 268,000</b>	<b>\$ 7,000</b>	<b>\$ -</b>	<b>\$ 442,000</b>	<b>\$ (358,000)</b>
<i>GT 5-6</i>						
CTGs and HRSGs	\$ 3,353,000	\$ 5,389,000	\$ -	\$ -	\$ 8,742,000	\$ -
Steam Turbine & Building	\$ 20,000	\$ 33,000	\$ -	\$ -	\$ 53,000	\$ -
SCR	\$ 79,000	\$ 127,000	\$ -	\$ -	\$ 206,000	\$ -
Flood Wall	\$ 266,000	\$ 427,000	\$ -	\$ -	\$ 693,000	\$ -
Cooling Towers & Basin	\$ 278,000	\$ 446,000	\$ -	\$ -	\$ 724,000	\$ -
GSU & Foundation	\$ 88,000	\$ 141,000	\$ -	\$ -	\$ 229,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 79,000	\$ -	\$ 79,000	\$ -
Debris	\$ -	\$ -	\$ 10,000	\$ -	\$ 10,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (6,079,000)
<b>Subtotal</b>	<b>\$ 4,084,000</b>	<b>\$ 6,563,000</b>	<b>\$ 89,000</b>	<b>\$ -</b>	<b>\$ 10,736,000</b>	<b>\$ (6,079,000)</b>
<i>Handling</i>						
Coal Handling Facilities	\$ 387,000	\$ 621,000	\$ -	\$ -	\$ 1,008,000	\$ -
Coal Storage Area Restoration	\$ -	\$ -	\$ -	\$ 7,958,000	\$ 7,958,000	\$ -
Limestone Handling Facilities	\$ 30,000	\$ 49,000	\$ -	\$ -	\$ 79,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 13,000	\$ -	\$ 13,000	\$ -
Debris	\$ -	\$ -	\$ 33,000	\$ -	\$ 33,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (267,000)
<b>Subtotal</b>	<b>\$ 417,000</b>	<b>\$ 670,000</b>	<b>\$ 46,000</b>	<b>\$ 7,958,000</b>	<b>\$ 9,091,000</b>	<b>\$ (267,000)</b>
<i>Common</i>						
Cooling Water Intakes and Circulating Water Pumps	\$ 150,000	\$ 242,000	\$ -	\$ -	\$ 392,000	\$ -
BOP Misc.	\$ 32,000	\$ 51,000	\$ -	\$ -	\$ 83,000	\$ -
Roads	\$ 168,000	\$ 270,000	\$ -	\$ -	\$ 438,000	\$ -
All BOP Buildings	\$ 336,000	\$ 541,000	\$ -	\$ -	\$ 877,000	\$ -
Fuel Equipment	\$ 482,000	\$ 775,000	\$ -	\$ -	\$ 1,257,000	\$ -
All Other Tanks	\$ 578,000	\$ 930,000	\$ -	\$ -	\$ 1,508,000	\$ -
Transformers & Foundation	\$ -	\$ -	\$ -	\$ 298,000	\$ 298,000	\$ -
Refractory Disposal	\$ -	\$ -	\$ -	\$ 15,000	\$ 15,000	\$ -
Mercury & Universal Waste Disposal	\$ -	\$ -	\$ -	\$ 17,000	\$ 17,000	\$ -
Fuel Oil Tank Area Remediation	\$ -	\$ -	\$ -	\$ 365,000	\$ 365,000	\$ -
Fuel Oil Line Flushing/Cleaning	\$ -	\$ -	\$ -	\$ 52,000	\$ 52,000	\$ -
Pond Closure	\$ -	\$ -	\$ -	\$ 25,413,000	\$ 25,413,000	\$ -
Gypsum Area	\$ -	\$ -	\$ -	\$ 14,904,000	\$ 14,904,000	\$ -
Plant Washdown & Materials Disposal	\$ -	\$ -	\$ -	\$ 41,000	\$ 41,000	\$ -
Concrete Removal, Crushing, & Disposal	\$ -	\$ -	\$ 92,000	\$ -	\$ 92,000	\$ -
Grading & Seeding	\$ -	\$ -	\$ -	\$ 5,485,000	\$ 5,485,000	\$ -
Debris	\$ -	\$ -	\$ 14,000	\$ -	\$ 14,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (460,000)
<b>Subtotal</b>	<b>\$ 1,746,000</b>	<b>\$ 2,809,000</b>	<b>\$ 106,000</b>	<b>\$ 46,590,000</b>	<b>\$ 51,251,000</b>	<b>\$ (460,000)</b>
<b>Big Bend Subtotal</b>	<b>\$ 11,461,000</b>	<b>\$ 18,423,000</b>	<b>\$ 847,000</b>	<b>\$ 56,119,000</b>	<b>\$ 86,850,000</b>	<b>\$ (13,018,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 86,850,000</b>	<b>\$ (13,018,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					\$ -	\$ -
<b>CONTINGENCY (0%)</b>					\$ -	\$ -
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 86,850,000</b>	<b>\$ (13,018,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 73,832,000</b>	

Table A-6  
Big Bend Floating Solar  
Solar Decommissioning Cost Summary

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Big Bend Floating Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 20,800	\$ 21,700	\$ 7,000	\$ -	\$ 49,500	\$ -
Panel Supports/Rack	\$ 19,500	\$ 20,300	\$ -	\$ -	\$ 39,800	\$ -
Floats, Supports and Walkway	\$ 3,200	\$ 3,300	\$ -	\$ -	\$ 6,500	\$ -
Electrical & Wiring	\$ 200	\$ 200	\$ -	\$ -	\$ 400	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 100	\$ 100	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (76,100)
<b>Subtotal</b>	<b>\$ 43,700</b>	<b>\$ 45,500</b>	<b>\$ 10,200</b>	<b>\$ 100</b>	<b>\$ 99,500</b>	<b>\$ (76,100)</b>
<b>Big Bend Floating Solar Subtotal</b>	<b>\$ 43,700</b>	<b>\$ 45,500</b>	<b>\$ 10,200</b>	<b>\$ 100</b>	<b>\$ 99,500</b>	<b>\$ (76,100)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 99,500</b>	<b>\$ (76,100)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENCY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 99,500</b>	<b>\$ (76,100)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 23,400</b>	

**Table A-7**  
**Big Bend Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Big Bend Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 959,800	\$ 999,800	\$ 334,800	\$ -	\$ 2,294,400	\$ -
Panel Supports/Rack	\$ 528,400	\$ 550,400	\$ -	\$ -	\$ 1,078,800	\$ -
Battery Energy Storage System	\$ 28,800	\$ 21,900	\$ 29,500	\$ -	\$ 80,200	\$ -
Electrical & Wiring	\$ 111,500	\$ 116,200	\$ -	\$ -	\$ 227,700	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 632,100	\$ 632,100	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 5,400	\$ -	\$ 5,400	\$ -
Debris	\$ -	\$ -	\$ 2,700	\$ -	\$ 2,700	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (969,700)
<b>Subtotal</b>	<b>\$ 1,628,500</b>	<b>\$ 1,688,300</b>	<b>\$ 372,400</b>	<b>\$ 632,100</b>	<b>\$ 4,321,300</b>	<b>\$ (969,700)</b>
<b>Big Bend Solar Subtotal</b>	<b>\$ 1,628,500</b>	<b>\$ 1,688,300</b>	<b>\$ 372,400</b>	<b>\$ 632,100</b>	<b>\$ 4,321,300</b>	<b>\$ (969,700)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 4,321,300</b>	<b>\$ (969,700)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENCY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 4,321,300</b>	<b>\$ (969,700)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 3,351,600</b>	

**Table A-8**  
**Big Bend Solar Phase 2**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Big Bend Solar Phase 2</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 294,200	\$ 306,500	\$ -	\$ -	\$ 600,700	\$ -
Panel Supports/Rack	\$ 283,600	\$ 295,400	\$ -	\$ -	\$ 579,000	\$ -
Electrical & Wiring	\$ 97,600	\$ 101,600	\$ -	\$ -	\$ 199,200	\$ -
Site Restoration	\$ 37,200	\$ 38,800	\$ -	\$ 142,500	\$ 218,500	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 6,000	\$ -	\$ 6,000	\$ -
Debris	\$ -	\$ -	\$ 1,800	\$ -	\$ 1,800	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (537,900)
<b>Subtotal</b>	<b>\$ 712,600</b>	<b>\$ 742,300</b>	<b>\$ 7,800</b>	<b>\$ 142,500</b>	<b>\$ 1,605,200</b>	<b>\$ (537,900)</b>
<b>Big Bend Solar Phase 2 Subtotal</b>	<b>\$ 712,600</b>	<b>\$ 742,300</b>	<b>\$ 7,800</b>	<b>\$ 142,500</b>	<b>\$ 1,605,200</b>	<b>\$ (537,900)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 1,605,200</b>	<b>\$ (537,900)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 1,605,200</b>	<b>\$ (537,900)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 1,067,300</b>	

**Table A-9**  
**Bonnie Mine Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Bonnie Mine Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 971,700	\$ 1,012,200	\$ 306,400	\$ -	\$ 2,290,300	\$ -
Panel Supports/Rack	\$ 1,421,000	\$ 1,480,200	\$ -	\$ -	\$ 2,901,200	\$ -
Electrical & Wiring	\$ 82,300	\$ 85,600	\$ -	\$ -	\$ 167,900	\$ -
Site Restoration	\$ 70,900	\$ 73,900	\$ -	\$ 1,753,100	\$ 1,897,900	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 2,900	\$ -	\$ 2,900	\$ -
Debris	\$ -	\$ -	\$ 4,800	\$ -	\$ 4,800	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,211,400)
<b>Subtotal</b>	<b>\$ 2,545,900</b>	<b>\$ 2,651,900</b>	<b>\$ 314,100</b>	<b>\$ 1,753,100</b>	<b>\$ 7,265,000</b>	<b>\$ (2,211,400)</b>
<b>Bonnie Mine Solar Subtotal</b>	<b>\$ 2,545,900</b>	<b>\$ 2,651,900</b>	<b>\$ 314,100</b>	<b>\$ 1,753,100</b>	<b>\$ 7,265,000</b>	<b>\$ (2,211,400)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 7,265,000</b>	<b>\$ (2,211,400)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 7,265,000</b>	<b>\$ (2,211,400)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 5,053,600</b>	

**Table A-10**  
**Brewster Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Brewster Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 819,600	\$ 853,700	\$ 277,200	\$ -	\$ 1,950,500	\$ -
Panel Supports/Rack	\$ 892,400	\$ 929,600	\$ -	\$ -	\$ 1,822,000	\$ -
Electrical & Wiring	\$ 160,600	\$ 167,200	\$ -	\$ -	\$ 327,800	\$ -
Site Restoration	\$ 100,200	\$ 104,300	\$ -	\$ 1,277,300	\$ 1,481,800	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 9,800	\$ -	\$ 9,800	\$ -
Debris	\$ -	\$ -	\$ 2,600	\$ -	\$ 2,600	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (1,591,800)
<b>Subtotal</b>	<b>\$ 1,972,800</b>	<b>\$ 2,054,800</b>	<b>\$ 289,600</b>	<b>\$ 1,277,300</b>	<b>\$ 5,594,500</b>	<b>\$ (1,591,800)</b>
<b>Brewster Solar Subtotal</b>	<b>\$ 1,972,800</b>	<b>\$ 2,054,800</b>	<b>\$ 289,600</b>	<b>\$ 1,277,300</b>	<b>\$ 5,594,500</b>	<b>\$ (1,591,800)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 5,594,500</b>	<b>\$ (1,591,800)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 5,594,500</b>	<b>\$ (1,591,800)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 4,002,700</b>	

**Table A-11**  
**Bull Frog Creek Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Bull Frog Creek Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,540,100	\$ 1,604,200	\$ 413,400	\$ -	\$ 3,557,700	\$ -
Panel Supports/Rack	\$ 1,676,900	\$ 1,746,800	\$ -	\$ -	\$ 3,423,700	\$ -
Electrical & Wiring	\$ 146,900	\$ 152,900	\$ -	\$ -	\$ 299,800	\$ -
Site Restoration	\$ 188,200	\$ 196,100	\$ -	\$ 2,400,100	\$ 2,784,400	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 8,200	\$ -	\$ 8,200	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,567,900)
<b>Subtotal</b>	<b>\$ 3,552,100</b>	<b>\$ 3,700,000</b>	<b>\$ 424,800</b>	<b>\$ 2,400,100</b>	<b>\$ 10,077,000</b>	<b>\$ (2,567,900)</b>
<b>Bull Frog Creek Solar Subtotal</b>	<b>\$ 3,552,100</b>	<b>\$ 3,700,000</b>	<b>\$ 424,800</b>	<b>\$ 2,400,100</b>	<b>\$ 10,077,000</b>	<b>\$ (2,567,900)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 10,077,000</b>	<b>\$ (2,567,900)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 10,077,000</b>	<b>\$ (2,567,900)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,509,100</b>	

**Table A-12**  
**Cotton Mouth Ranch Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Cotton Mouth Ranch Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,555,200	\$ 1,619,900	\$ 648,000	\$ -	\$ 3,823,100	\$ -
Panel Supports/Rack	\$ 1,693,300	\$ 1,763,900	\$ -	\$ -	\$ 3,457,200	\$ -
Electrical & Wiring	\$ 148,200	\$ 154,500	\$ -	\$ -	\$ 302,700	\$ -
Site Restoration	\$ 190,100	\$ 198,000	\$ -	\$ 2,423,600	\$ 2,811,700	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 8,300	\$ -	\$ 8,300	\$ -
Debris	\$ -	\$ -	\$ 5,100	\$ -	\$ 5,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,550,600)
<b>Subtotal</b>	<b>\$ 3,586,800</b>	<b>\$ 3,736,300</b>	<b>\$ 661,400</b>	<b>\$ 2,423,600</b>	<b>\$ 10,408,100</b>	<b>\$ (2,550,600)</b>
<b>Cotton Mouth Ranch Solar Subtotal</b>	<b>\$ 3,586,800</b>	<b>\$ 3,736,300</b>	<b>\$ 661,400</b>	<b>\$ 2,423,600</b>	<b>\$ 10,408,100</b>	<b>\$ (2,550,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 10,408,100</b>	<b>\$ (2,550,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 10,408,100</b>	<b>\$ (2,550,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,857,500</b>	



**Table A-13**  
**Durrance Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Durrance Solar</b>						
<i>Solar Farm</i>						
O&M Building	\$ 3,000	\$ 3,100	\$ -	\$ -	\$ 6,100	\$ -
Solar Panel Removal	\$ 1,627,600	\$ 1,695,400	\$ 602,600	\$ -	\$ 3,925,600	\$ -
Panel Supports/Rack	\$ 3,158,000	\$ 3,289,500	\$ -	\$ -	\$ 6,447,500	\$ -
Electrical & Wiring	\$ 118,000	\$ 122,800	\$ -	\$ -	\$ 240,800	\$ -
Site Restoration	\$ 83,400	\$ 86,800	\$ -	\$ 1,369,900	\$ 1,540,100	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 7,300	\$ -	\$ 7,300	\$ -
Debris	\$ -	\$ -	\$ 1,600	\$ -	\$ 1,600	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,340,200)
<b>Subtotal</b>	<b>\$ 4,990,000</b>	<b>\$ 5,197,600</b>	<b>\$ 611,500</b>	<b>\$ 1,369,900</b>	<b>\$ 12,169,000</b>	<b>\$ (4,340,200)</b>
<b>Durrance Solar Subtotal</b>	<b>\$ 4,990,000</b>	<b>\$ 5,197,600</b>	<b>\$ 611,500</b>	<b>\$ 1,369,900</b>	<b>\$ 12,169,000</b>	<b>\$ (4,340,200)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 12,169,000</b>	<b>\$ (4,340,200)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 12,169,000</b>	<b>\$ (4,340,200)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,828,800</b>	

**Table A-14**  
**Eastern PVS+ES Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Eastern PVS+ES Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 12,600	\$ 13,100	\$ 3,200	\$ -	\$ 28,900	\$ -
Panel Supports/Rack	\$ 13,200	\$ 13,800	\$ -	\$ -	\$ 27,000	\$ -
Battery Containers and Racks	\$ 3,200	\$ 3,300	\$ 6,700	\$ -	\$ 13,200	\$ -
Electrical & Wiring	\$ 2,500	\$ 2,500	\$ -	\$ -	\$ 5,000	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 19,900	\$ 19,900	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 11,200	\$ -	\$ 11,200	\$ -
Debris	\$ -	\$ -	\$ 100	\$ -	\$ 100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (33,700)
<b>Subtotal</b>	<b>\$ 31,500</b>	<b>\$ 32,700</b>	<b>\$ 21,200</b>	<b>\$ 19,900</b>	<b>\$ 105,300</b>	<b>\$ (33,700)</b>
<b>Eastern PVS+ES Solar Subtotal</b>	<b>\$ 31,500</b>	<b>\$ 32,700</b>	<b>\$ 21,200</b>	<b>\$ 19,900</b>	<b>\$ 105,300</b>	<b>\$ (33,700)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 105,300</b>	<b>\$ (33,700)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 105,300</b>	<b>\$ (33,700)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 71,600</b>	

**Table A-15**  
**English Creek Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>English Creek Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,567,600	\$ 1,632,900	\$ 495,700	\$ -	\$ 3,696,200	\$ -
Panel Supports/Rack	\$ 1,641,200	\$ 1,709,600	\$ -	\$ -	\$ 3,350,800	\$ -
Electrical & Wiring	\$ 194,800	\$ 202,800	\$ -	\$ -	\$ 397,600	\$ -
Site Restoration	\$ 189,000	\$ 196,800	\$ -	\$ 1,578,300	\$ 1,964,100	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 12,400	\$ -	\$ 12,400	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,546,600)
<b>Subtotal</b>	<b>\$ 3,592,600</b>	<b>\$ 3,742,100</b>	<b>\$ 511,300</b>	<b>\$ 1,578,300</b>	<b>\$ 9,424,300</b>	<b>\$ (2,546,600)</b>
<b>English Creek Solar Subtotal</b>	<b>\$ 3,592,600</b>	<b>\$ 3,742,100</b>	<b>\$ 511,300</b>	<b>\$ 1,578,300</b>	<b>\$ 9,424,300</b>	<b>\$ (2,546,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 9,424,300</b>	<b>\$ (2,546,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 9,424,300</b>	<b>\$ (2,546,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 6,877,700</b>	

**Table A-16**  
**Florida Aquarium Pavillion Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Florida Aquarium Pavillion Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 3,200	\$ 3,300	\$ 1,000	\$ -	\$ 7,500	\$ -
Panel Supports/Rack	\$ 800	\$ 800	\$ -	\$ -	\$ 1,600	\$ -
Battery Containers and Racks	\$ -	\$ -	\$ 200	\$ -	\$ 200	\$ -
Electrical & Wiring	\$ 300	\$ 300	\$ -	\$ -	\$ 600	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 2,800	\$ 2,800	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (5,000)
<b>Subtotal</b>	<b>\$ 4,300</b>	<b>\$ 4,400</b>	<b>\$ 1,200</b>	<b>\$ 2,800</b>	<b>\$ 12,700</b>	<b>\$ (5,000)</b>
<b>Florida Aquarium Pavillion Solar Subtotal</b>	<b>\$ 4,300</b>	<b>\$ 4,400</b>	<b>\$ 1,200</b>	<b>\$ 2,800</b>	<b>\$ 12,700</b>	<b>\$ (5,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 12,700</b>	<b>\$ (5,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 12,700</b>	<b>\$ (5,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,700</b>	

**Table A-17**  
**Future Solar Site I**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Future Solar Site I</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,529,400	\$ 1,593,100	\$ 485,400	\$ -	\$ 3,607,900	\$ -
Panel Supports/Rack	\$ 1,449,200	\$ 1,509,500	\$ -	\$ -	\$ 2,958,700	\$ -
Electrical & Wiring	\$ 190,100	\$ 198,000	\$ -	\$ -	\$ 388,100	\$ -
Site Restoration	\$ 184,400	\$ 192,000	\$ -	\$ 3,155,300	\$ 3,531,700	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 12,100	\$ -	\$ 12,100	\$ -
Debris	\$ -	\$ -	\$ 3,100	\$ -	\$ 3,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,367,300)
<b>Subtotal</b>	<b>\$ 3,353,100</b>	<b>\$ 3,492,600</b>	<b>\$ 500,600</b>	<b>\$ 3,155,300</b>	<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>Future Solar Site I Subtotal</b>	<b>\$ 3,353,100</b>	<b>\$ 3,492,600</b>	<b>\$ 500,600</b>	<b>\$ 3,155,300</b>	<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 8,134,300</b>	

**Table A-18**  
**Future Solar Site II**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Future Solar Site II</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,529,400	\$ 1,593,100	\$ 485,400	\$ -	\$ 3,607,900	\$ -
Panel Supports/Rack	\$ 1,449,200	\$ 1,509,500	\$ -	\$ -	\$ 2,958,700	\$ -
Electrical & Wiring	\$ 190,100	\$ 198,000	\$ -	\$ -	\$ 388,100	\$ -
Site Restoration	\$ 184,400	\$ 192,000	\$ -	\$ 3,155,300	\$ 3,531,700	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 12,100	\$ -	\$ 12,100	\$ -
Debris	\$ -	\$ -	\$ 3,100	\$ -	\$ 3,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,367,300)
<b>Subtotal</b>	<b>\$ 3,353,100</b>	<b>\$ 3,492,600</b>	<b>\$ 500,600</b>	<b>\$ 3,155,300</b>	<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>Future Solar Site II Subtotal</b>	<b>\$ 3,353,100</b>	<b>\$ 3,492,600</b>	<b>\$ 500,600</b>	<b>\$ 3,155,300</b>	<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 10,501,600</b>	<b>\$ (2,367,300)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 8,134,300</b>	

**Table A-19**  
**Grange Hall Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Grange Hall Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,670,100	\$ 1,739,600	\$ 604,600	\$ -	\$ 4,014,300	\$ -
Panel Supports/Rack	\$ 2,578,500	\$ 2,685,900	\$ -	\$ -	\$ 5,264,400	\$ -
Electrical & Wiring	\$ 80,400	\$ 83,800	\$ -	\$ -	\$ 164,200	\$ -
Site Restoration	\$ 78,500	\$ 81,800	\$ -	\$ 1,475,500	\$ 1,635,800	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 3,000	\$ -	\$ 3,000	\$ -
Debris	\$ -	\$ -	\$ 4,400	\$ -	\$ 4,400	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (3,628,000)
<b>Subtotal</b>	<b>\$ 4,407,500</b>	<b>\$ 4,591,100</b>	<b>\$ 612,000</b>	<b>\$ 1,475,500</b>	<b>\$ 11,086,100</b>	<b>\$ (3,628,000)</b>
<b>Grange Hall Solar Subtotal</b>	<b>\$ 4,407,500</b>	<b>\$ 4,591,100</b>	<b>\$ 612,000</b>	<b>\$ 1,475,500</b>	<b>\$ 11,086,100</b>	<b>\$ (3,628,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 11,086,100</b>	<b>\$ (3,628,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 11,086,100</b>	<b>\$ (3,628,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,458,100</b>	

**Table A-20**  
**Jamison Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Jamison Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,522,600	\$ 1,586,000	\$ 563,700	\$ -	\$ 3,672,300	\$ -
Panel Supports/Rack	\$ 1,616,900	\$ 1,684,300	\$ -	\$ -	\$ 3,301,200	\$ -
Electrical & Wiring	\$ 321,300	\$ 334,600	\$ -	\$ -	\$ 655,900	\$ -
Site Restoration	\$ 199,700	\$ 208,100	\$ -	\$ 3,124,300	\$ 3,532,100	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 10,000	\$ -	\$ 10,000	\$ -
Debris	\$ -	\$ -	\$ 4,100	\$ -	\$ 4,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (3,500,400)
<b>Subtotal</b>	<b>\$ 3,660,500</b>	<b>\$ 3,813,000</b>	<b>\$ 577,800</b>	<b>\$ 3,124,300</b>	<b>\$ 11,175,600</b>	<b>\$ (3,500,400)</b>
<b>Jamison Solar Subtotal</b>	<b>\$ 3,660,500</b>	<b>\$ 3,813,000</b>	<b>\$ 577,800</b>	<b>\$ 3,124,300</b>	<b>\$ 11,175,600</b>	<b>\$ (3,500,400)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 11,175,600</b>	<b>\$ (3,500,400)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 11,175,600</b>	<b>\$ (3,500,400)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 7,675,200</b>	



**Table A-21**  
**Juniper Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Juniper Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,454,200	\$ 1,514,800	\$ 511,800	\$ -	\$ 3,480,800	\$ -
Panel Supports/Rack	\$ 1,522,600	\$ 1,586,000	\$ -	\$ -	\$ 3,108,600	\$ -
Electrical & Wiring	\$ 179,700	\$ 187,100	\$ -	\$ -	\$ 366,800	\$ -
Site Restoration	\$ 175,300	\$ 182,600	\$ -	\$ 3,499,700	\$ 3,857,600	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 11,400	\$ -	\$ 11,400	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,332,300)
<b>Subtotal</b>	<b>\$ 3,331,800</b>	<b>\$ 3,470,500</b>	<b>\$ 526,400</b>	<b>\$ 3,499,700</b>	<b>\$ 10,828,400</b>	<b>\$ (2,332,300)</b>
<b>Juniper Solar Subtotal</b>	<b>\$ 3,331,800</b>	<b>\$ 3,470,500</b>	<b>\$ 526,400</b>	<b>\$ 3,499,700</b>	<b>\$ 10,828,400</b>	<b>\$ (2,332,300)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 10,828,400</b>	<b>\$ (2,332,300)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 10,828,400</b>	<b>\$ (2,332,300)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 8,496,100</b>	

**Table A-22**  
**Lake Hancock Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Lake Hancock Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,300,900	\$ 1,355,100	\$ 414,500	\$ -	\$ 3,070,500	\$ -
Panel Supports/Rack	\$ 2,009,700	\$ 2,093,400	\$ -	\$ -	\$ 4,103,100	\$ -
Electrical & Wiring	\$ 72,800	\$ 75,900	\$ -	\$ -	\$ 148,700	\$ -
Site Restoration	\$ 44,800	\$ 46,700	\$ -	\$ 1,341,100	\$ 1,432,600	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 2,800	\$ -	\$ 2,800	\$ -
Debris	\$ -	\$ -	\$ 3,300	\$ -	\$ 3,300	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,889,500)
<b>Subtotal</b>	<b>\$ 3,428,200</b>	<b>\$ 3,571,100</b>	<b>\$ 420,600</b>	<b>\$ 1,341,100</b>	<b>\$ 8,761,000</b>	<b>\$ (2,889,500)</b>
<b>Lake Hancock Solar Subtotal</b>	<b>\$ 3,428,200</b>	<b>\$ 3,571,100</b>	<b>\$ 420,600</b>	<b>\$ 1,341,100</b>	<b>\$ 8,761,000</b>	<b>\$ (2,889,500)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 8,761,000</b>	<b>\$ (2,889,500)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 8,761,000</b>	<b>\$ (2,889,500)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 5,871,500</b>	

**Table A-23**  
**Lake Mabel Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Lake Mabel Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,547,700	\$ 1,612,200	\$ 526,700	\$ -	\$ 3,686,600	\$ -
Panel Supports/Rack	\$ 1,620,400	\$ 1,687,900	\$ -	\$ -	\$ 3,308,300	\$ -
Battery Energy Storage System	\$ 193,400	\$ 153,800	\$ 172,800	\$ -	\$ 520,000	\$ -
Electrical & Wiring	\$ 192,200	\$ 200,300	\$ -	\$ -	\$ 392,500	\$ -
Site Restoration	\$ 186,600	\$ 194,300	\$ -	\$ 2,963,300	\$ 3,344,200	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 14,900	\$ -	\$ 14,900	\$ -
Debris	\$ -	\$ -	\$ 3,400	\$ -	\$ 3,400	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (3,121,600)
<b>Subtotal</b>	<b>\$ 3,740,300</b>	<b>\$ 3,848,500</b>	<b>\$ 717,800</b>	<b>\$ 2,963,300</b>	<b>\$ 11,269,900</b>	<b>\$ (3,121,600)</b>
<b>Lake Mabel Solar Subtotal</b>	<b>\$ 3,740,300</b>	<b>\$ 3,848,500</b>	<b>\$ 717,800</b>	<b>\$ 2,963,300</b>	<b>\$ 11,269,900</b>	<b>\$ (3,121,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 11,269,900</b>	<b>\$ (3,121,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENCY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 11,269,900</b>	<b>\$ (3,121,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 8,148,300</b>	

**Table A-24**  
**Laurel Oaks Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Laurel Oaks Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,296,700	\$ 1,350,700	\$ 430,400	\$ -	\$ 3,077,800	\$ -
Panel Supports/Rack	\$ 1,376,000	\$ 1,433,300	\$ -	\$ -	\$ 2,809,300	\$ -
Electrical & Wiring	\$ 121,100	\$ 126,000	\$ -	\$ -	\$ 247,100	\$ -
Site Restoration	\$ 112,400	\$ 117,100	\$ -	\$ 1,931,700	\$ 2,161,200	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 6,400	\$ -	\$ 6,400	\$ -
Debris	\$ -	\$ -	\$ 4,100	\$ -	\$ 4,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,217,600)
<b>Subtotal</b>	<b>\$ 2,906,200</b>	<b>\$ 3,027,100</b>	<b>\$ 440,900</b>	<b>\$ 1,931,700</b>	<b>\$ 8,305,900</b>	<b>\$ (2,217,600)</b>
<b>Laurel Oaks Solar Subtotal</b>	<b>\$ 2,906,200</b>	<b>\$ 3,027,100</b>	<b>\$ 440,900</b>	<b>\$ 1,931,700</b>	<b>\$ 8,305,900</b>	<b>\$ (2,217,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 8,305,900</b>	<b>\$ (2,217,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 8,305,900</b>	<b>\$ (2,217,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 6,088,300</b>	

**Table A-25**  
**Legoland Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Legoland Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 27,800	\$ 29,000	\$ 9,500	\$ -	\$ 66,300	\$ -
Panel Supports/Rack	\$ 13,400	\$ 13,900	\$ -	\$ -	\$ 27,300	\$ -
Electrical & Wiring	\$ 25,400	\$ 26,400	\$ -	\$ -	\$ 51,800	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 24,600	\$ 24,600	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 1,900	\$ -	\$ 1,900	\$ -
Debris	\$ -	\$ -	\$ 200	\$ -	\$ 200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (31,100)
<b>Subtotal</b>	<b>\$ 66,600</b>	<b>\$ 69,300</b>	<b>\$ 11,600</b>	<b>\$ 24,600</b>	<b>\$ 172,100</b>	<b>\$ (31,100)</b>
<b>Legoland Solar Subtotal</b>	<b>\$ 66,600</b>	<b>\$ 69,300</b>	<b>\$ 11,600</b>	<b>\$ 24,600</b>	<b>\$ 172,100</b>	<b>\$ (31,100)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 172,100</b>	<b>\$ (31,100)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 172,100</b>	<b>\$ (31,100)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 141,000</b>	

**Table A-26**  
**Lithia Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Lithia Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 2,081,000	\$ 2,167,600	\$ 736,200	\$ -	\$ 4,984,800	\$ -
Panel Supports/Rack	\$ 2,656,300	\$ 2,766,900	\$ -	\$ -	\$ 5,423,200	\$ -
Electrical & Wiring	\$ 152,900	\$ 159,300	\$ -	\$ -	\$ 312,200	\$ -
Site Restoration	\$ 80,900	\$ 84,200	\$ -	\$ 2,632,900	\$ 2,798,000	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Debris	\$ -	\$ -	\$ 15,100	\$ -	\$ 15,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,272,200)
<b>Subtotal</b>	<b>\$ 4,971,100</b>	<b>\$ 5,178,000</b>	<b>\$ 754,500</b>	<b>\$ 2,632,900</b>	<b>\$ 13,536,500</b>	<b>\$ (4,272,200)</b>
<b>Lithia Solar Subtotal</b>	<b>\$ 4,971,100</b>	<b>\$ 5,178,000</b>	<b>\$ 754,500</b>	<b>\$ 2,632,900</b>	<b>\$ 13,536,500</b>	<b>\$ (4,272,200)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 13,536,500</b>	<b>\$ (4,272,200)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 13,536,500</b>	<b>\$ (4,272,200)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 9,264,300</b>	

**Table A-27**  
**Little Manatee River**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Little Manatee River</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 2,055,400	\$ 2,141,000	\$ 727,100	\$ -	\$ 4,923,500	\$ -
Panel Supports/Rack	\$ 2,970,500	\$ 3,094,200	\$ -	\$ -	\$ 6,064,700	\$ -
Electrical & Wiring	\$ 138,100	\$ 143,900	\$ -	\$ -	\$ 282,000	\$ -
Site Restoration	\$ 105,300	\$ 109,700	\$ -	\$ 2,662,500	\$ 2,877,500	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 2,900	\$ -	\$ 2,900	\$ -
Debris	\$ -	\$ -	\$ 13,300	\$ -	\$ 13,300	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,602,400)
<b>Subtotal</b>	<b>\$ 5,271,000</b>	<b>\$ 5,490,600</b>	<b>\$ 743,300</b>	<b>\$ 2,662,500</b>	<b>\$ 14,167,400</b>	<b>\$ (4,602,400)</b>
<b>Little Manatee River Subtotal</b>	<b>\$ 5,271,000</b>	<b>\$ 5,490,600</b>	<b>\$ 743,300</b>	<b>\$ 2,662,500</b>	<b>\$ 14,167,400</b>	<b>\$ (4,602,400)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 14,167,400</b>	<b>\$ (4,602,400)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 14,167,400</b>	<b>\$ (4,602,400)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 9,565,000</b>	

Table A-28  
MacDill RICE and BESS  
Decommissioning Cost Summary

MacDill RICE and BESS	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<i>Unit 1 and 2</i>						
CTGs and HRSGs	\$ 72,000	\$ 116,000	\$ -	\$ -	\$ 188,000	\$ -
Steam Turbine & Building	\$ 59,000	\$ 94,000	\$ -	\$ -	\$ 153,000	\$ -
SCR	\$ 50,000	\$ 81,000	\$ -	\$ -	\$ 131,000	\$ -
Stacks	\$ 8,000	\$ 13,000	\$ -	\$ -	\$ 21,000	\$ -
GSU & Foundation	\$ 3,000	\$ 5,000	\$ -	\$ -	\$ 8,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 29,000	\$ -	\$ 29,000	\$ -
Debris	\$ -	\$ -	\$ 4,000	\$ -	\$ 4,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (287,000)
<b>Subtotal</b>	<b>\$ 192,000</b>	<b>\$ 309,000</b>	<b>\$ 33,000</b>	<b>\$ -</b>	<b>\$ 534,000</b>	<b>\$ (287,000)</b>
<i>Unit 3 and 4</i>						
CTGs and HRSGs	\$ 72,000	\$ 116,000	\$ -	\$ -	\$ 188,000	\$ -
Steam Turbine & Building	\$ 59,000	\$ 94,000	\$ -	\$ -	\$ 153,000	\$ -
SCR	\$ 50,000	\$ 81,000	\$ -	\$ -	\$ 131,000	\$ -
Stacks	\$ 8,000	\$ 13,000	\$ -	\$ -	\$ 21,000	\$ -
GSU & Foundation	\$ 3,000	\$ 5,000	\$ -	\$ -	\$ 8,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 29,000	\$ -	\$ 29,000	\$ -
Debris	\$ -	\$ -	\$ 4,000	\$ -	\$ 4,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (287,000)
<b>Subtotal</b>	<b>\$ 192,000</b>	<b>\$ 309,000</b>	<b>\$ 33,000</b>	<b>\$ -</b>	<b>\$ 534,000</b>	<b>\$ (287,000)</b>
<i>BESS</i>						
Battery Containers and Racks	\$ 263,000	\$ 187,000	\$ -	\$ -	\$ 450,000	\$ -
Electrical & Wiring	\$ 11,000	\$ 17,000	\$ -	\$ -	\$ 28,000	\$ -
Site Restoration	\$ 27,000	\$ 43,000	\$ -	\$ -	\$ 70,000	\$ -
Grading & Seeding	\$ -	\$ -	\$ -	\$ 12,000	\$ 12,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 5,000	\$ -	\$ 5,000	\$ -
Debris	\$ -	\$ -	\$ 4,000	\$ -	\$ 4,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (318,000)
<b>Subtotal</b>	<b>\$ 301,000</b>	<b>\$ 247,000</b>	<b>\$ 9,000</b>	<b>\$ 12,000</b>	<b>\$ 569,000</b>	<b>\$ (318,000)</b>
<i>Common</i>						
BOP Misc.	\$ 49,000	\$ 79,000	\$ -	\$ -	\$ 128,000	\$ -
All Other Tanks	\$ 6,000	\$ 10,000	\$ -	\$ -	\$ 16,000	\$ -
Transformers & Foundation	\$ 44,000	\$ 71,000	\$ -	\$ -	\$ 115,000	\$ -
Pond Closure	\$ -	\$ -	\$ -	\$ 60,000	\$ 60,000	\$ -
Concrete Removal, Crushing, & Disposal	\$ -	\$ -	\$ 2,000	\$ -	\$ 2,000	\$ -
Grading & Seeding	\$ -	\$ -	\$ -	\$ 67,000	\$ 67,000	\$ -
Debris	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (375,000)
<b>Subtotal</b>	<b>\$ 99,000</b>	<b>\$ 160,000</b>	<b>\$ 2,000</b>	<b>\$ 127,000</b>	<b>\$ 388,000</b>	<b>\$ (375,000)</b>
<b>MacDill RICE and BESS Subtotal</b>	<b>\$ 784,000</b>	<b>\$ 1,025,000</b>	<b>\$ 77,000</b>	<b>\$ 139,000</b>	<b>\$ 2,025,000</b>	<b>\$ (1,267,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 2,025,000</b>	<b>\$ (1,267,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					\$ -	
<b>CONTINGENCY (0%)</b>					\$ -	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 2,025,000</b>	<b>\$ (1,267,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 758,000</b>	



**Table A-29**  
**Magnolia Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Magnolia Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,579,300	\$ 1,645,000	\$ 524,200	\$ -	\$ 3,748,500	\$ -
Panel Supports/Rack	\$ 1,683,900	\$ 1,754,000	\$ -	\$ -	\$ 3,437,900	\$ -
Electrical & Wiring	\$ 109,100	\$ 113,600	\$ -	\$ -	\$ 222,700	\$ -
Site Restoration	\$ 187,300	\$ 195,100	\$ -	\$ 4,350,500	\$ 4,732,900	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 5,600	\$ -	\$ 5,600	\$ -
Debris	\$ -	\$ -	\$ 3,700	\$ -	\$ 3,700	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,631,500)
<b>Subtotal</b>	<b>\$ 3,559,600</b>	<b>\$ 3,707,700</b>	<b>\$ 533,500</b>	<b>\$ 4,350,500</b>	<b>\$ 12,151,300</b>	<b>\$ (2,631,500)</b>
<b>Magnolia Solar Subtotal</b>	<b>\$ 3,559,600</b>	<b>\$ 3,707,700</b>	<b>\$ 533,500</b>	<b>\$ 4,350,500</b>	<b>\$ 12,151,300</b>	<b>\$ (2,631,500)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 12,151,300</b>	<b>\$ (2,631,500)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 12,151,300</b>	<b>\$ (2,631,500)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 9,519,800</b>	

**Table A-30**  
**Mountain View Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Mountain View Solar</b>						
<i>Solar Farm</i>						
O&M Building	\$ 2,600	\$ 2,700	\$ -	\$ -	\$ 5,300	\$ -
Solar Panel Removal	\$ 1,155,200	\$ 1,203,300	\$ 439,200	\$ -	\$ 2,797,700	\$ -
Panel Supports/Rack	\$ 1,158,500	\$ 1,206,700	\$ -	\$ -	\$ 2,365,200	\$ -
Battery Containers and Racks	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Electrical & Wiring	\$ 111,600	\$ 116,300	\$ -	\$ -	\$ 227,900	\$ -
Site Restoration	\$ 105,500	\$ 109,900	\$ -	\$ 1,581,300	\$ 1,796,700	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 5,400	\$ -	\$ 5,400	\$ -
Debris	\$ -	\$ -	\$ 3,800	\$ -	\$ 3,800	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (1,793,600)
<b>Subtotal</b>	<b>\$ 2,533,400</b>	<b>\$ 2,638,900</b>	<b>\$ 448,400</b>	<b>\$ 1,581,300</b>	<b>\$ 7,202,000</b>	<b>\$ (1,793,600)</b>
<b>Mountain View Solar Subtotal</b>	<b>\$ 2,533,400</b>	<b>\$ 2,638,900</b>	<b>\$ 448,400</b>	<b>\$ 1,581,300</b>	<b>\$ 7,202,000</b>	<b>\$ (1,793,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 7,202,000</b>	<b>\$ (1,793,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 7,202,000</b>	<b>\$ (1,793,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 5,408,400</b>	

**Table A-31**  
**Payne Creek Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Payne Creek Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,968,700	\$ 2,050,700	\$ 768,200	\$ -	\$ 4,787,600	\$ -
Panel Supports/Rack	\$ 2,787,000	\$ 2,903,100	\$ -	\$ -	\$ 5,690,100	\$ -
Electrical & Wiring	\$ 134,200	\$ 139,800	\$ -	\$ -	\$ 274,000	\$ -
Site Restoration	\$ 120,200	\$ 125,200	\$ -	\$ 2,457,400	\$ 2,702,800	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 5,100	\$ -	\$ 5,100	\$ -
Debris	\$ -	\$ -	\$ 8,800	\$ -	\$ 8,800	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,240,600)
<b>Subtotal</b>	<b>\$ 5,011,100</b>	<b>\$ 5,219,900</b>	<b>\$ 782,100</b>	<b>\$ 2,457,400</b>	<b>\$ 13,470,500</b>	<b>\$ (4,240,600)</b>
<b>Payne Creek Solar Subtotal</b>	<b>\$ 5,011,100</b>	<b>\$ 5,219,900</b>	<b>\$ 782,100</b>	<b>\$ 2,457,400</b>	<b>\$ 13,470,500</b>	<b>\$ (4,240,600)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 13,470,500</b>	<b>\$ (4,240,600)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 13,470,500</b>	<b>\$ (4,240,600)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 9,229,900</b>	

**Table A-32**  
**Peace Creek Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Peace Creek Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 1,515,600	\$ 1,578,700	\$ 485,400	\$ -	\$ 3,579,700	\$ -
Panel Supports/Rack	\$ 2,093,900	\$ 2,181,100	\$ -	\$ -	\$ 4,275,000	\$ -
Electrical & Wiring	\$ 116,700	\$ 121,500	\$ -	\$ -	\$ 238,200	\$ -
Site Restoration	\$ 83,500	\$ 87,000	\$ -	\$ 1,436,800	\$ 1,607,300	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 4,500	\$ -	\$ 4,500	\$ -
Debris	\$ -	\$ -	\$ 6,100	\$ -	\$ 6,100	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (3,300,700)
<b>Subtotal</b>	<b>\$ 3,811,000</b>	<b>\$ 3,969,600</b>	<b>\$ 496,000</b>	<b>\$ 1,436,800</b>	<b>\$ 9,713,400</b>	<b>\$ (3,300,700)</b>
<b>Peace Creek Solar Subtotal</b>	<b>\$ 3,811,000</b>	<b>\$ 3,969,600</b>	<b>\$ 496,000</b>	<b>\$ 1,436,800</b>	<b>\$ 9,713,400</b>	<b>\$ (3,300,700)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 9,713,400</b>	<b>\$ (3,300,700)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 9,713,400</b>	<b>\$ (3,300,700)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 6,412,700</b>	

**Table A-33**  
**Polk**  
**Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Polk</b>						
<i>Unit 1CA</i>						
CTGs and HRSGs	\$ 800,000	\$ 1,287,000	\$ -	\$ -	\$ 2,087,000	\$ -
Steam Turbine & Building	\$ 489,000	\$ 786,000	\$ -	\$ -	\$ 1,275,000	\$ -
SCR	\$ 34,000	\$ 55,000	\$ -	\$ -	\$ 89,000	\$ -
H2SO4 Plant	\$ 320,000	\$ 515,000	\$ -	\$ -	\$ 835,000	\$ -
Gassifer	\$ 866,000	\$ 1,392,000	\$ -	\$ -	\$ 2,258,000	\$ -
Stack	\$ 35,000	\$ 57,000	\$ -	\$ -	\$ 92,000	\$ -
GSU & Foundation	\$ 62,000	\$ 100,000	\$ -	\$ -	\$ 162,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 46,000	\$ -	\$ 46,000	\$ -
Debris	\$ -	\$ -	\$ 8,000	\$ -	\$ 8,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (5,422,000)
<b>Subtotal</b>	<b>\$ 2,606,000</b>	<b>\$ 4,192,000</b>	<b>\$ 54,000</b>	<b>\$ -</b>	<b>\$ 6,852,000</b>	<b>\$ (5,422,000)</b>
<i>Unit 2-5 CC</i>						
CTGs and HRSGs	\$ 2,892,000	\$ 4,649,000	\$ -	\$ -	\$ 7,541,000	\$ -
Steam Turbine & Building	\$ 350,000	\$ 562,000	\$ -	\$ -	\$ 912,000	\$ -
SCR	\$ 118,000	\$ 189,000	\$ -	\$ -	\$ 307,000	\$ -
Cooling Towers & Basin	\$ 216,000	\$ 347,000	\$ -	\$ -	\$ 563,000	\$ -
Stacks	\$ 141,000	\$ 227,000	\$ -	\$ -	\$ 368,000	\$ -
GSU & Foundation	\$ 196,000	\$ 315,000	\$ -	\$ -	\$ 511,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 4,000	\$ -	\$ 4,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (7,979,000)
<b>Subtotal</b>	<b>\$ 3,913,000</b>	<b>\$ 6,289,000</b>	<b>\$ 4,000</b>	<b>\$ -</b>	<b>\$ 10,206,000</b>	<b>\$ (7,979,000)</b>
<i>Handling</i>						
Coal Handling Facilities	\$ 370,000	\$ 594,000	\$ -	\$ -	\$ 964,000	\$ -
On-site Concrete Crushing & Disposal	\$ -	\$ -	\$ 15,000	\$ -	\$ 15,000	\$ -
Debris	\$ -	\$ -	\$ 43,000	\$ -	\$ 43,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (173,000)
<b>Subtotal</b>	<b>\$ 370,000</b>	<b>\$ 594,000</b>	<b>\$ 58,000</b>	<b>\$ -</b>	<b>\$ 1,022,000</b>	<b>\$ (173,000)</b>
<i>Common</i>						
Switchyard and Substation	\$ 21,000	\$ -	\$ -	\$ -	\$ 21,000	\$ -
Cooling Water Intakes and Circulating Water Pumps	\$ 41,000	\$ 66,000	\$ -	\$ 473,000	\$ 580,000	\$ -
BOP Misc.	\$ 633,000	\$ 1,018,000	\$ -	\$ -	\$ 1,651,000	\$ -
Roads	\$ 168,000	\$ 270,000	\$ 815,000	\$ -	\$ 1,253,000	\$ -
All BOP Buildings	\$ 3,000	\$ 5,000	\$ -	\$ -	\$ 8,000	\$ -
Fuel Equipment	\$ 163,000	\$ 262,000	\$ -	\$ -	\$ 425,000	\$ -
All Other Tanks	\$ 259,000	\$ 416,000	\$ -	\$ -	\$ 675,000	\$ -
Transformers & Foundation	\$ -	\$ -	\$ -	\$ 393,000	\$ 393,000	\$ -
Mercury & Universal Waste Disposal	\$ -	\$ -	\$ -	\$ 117,000	\$ 117,000	\$ -
Pond Closure	\$ -	\$ -	\$ -	\$ 1,358,000	\$ 1,358,000	\$ -
Fuel Oil Tank Area Remediation	\$ -	\$ -	\$ -	\$ 309,000	\$ 309,000	\$ -
Concrete Removal, Crushing, & Disposal	\$ -	\$ -	\$ 68,000	\$ -	\$ 68,000	\$ -
Grading & Seeding	\$ -	\$ -	\$ -	\$ 4,608,000	\$ 4,608,000	\$ -
Debris	\$ -	\$ -	\$ 6,000	\$ -	\$ 6,000	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (295,000)
<b>Subtotal</b>	<b>\$ 1,288,000</b>	<b>\$ 2,037,000</b>	<b>\$ 889,000</b>	<b>\$ 7,258,000</b>	<b>\$ 11,472,000</b>	<b>\$ (295,000)</b>
<b>Polk Subtotal</b>	<b>\$ 8,177,000</b>	<b>\$ 13,112,000</b>	<b>\$ 1,005,000</b>	<b>\$ 7,258,000</b>	<b>\$ 29,552,000</b>	<b>\$ (13,869,000)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 29,552,000</b>	<b>\$ (13,869,000)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 29,552,000</b>	<b>\$ (13,869,000)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 15,683,000</b>	

**Table A-34**  
**Riverside Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Riverside Solar</b>						
<i>Solar Farm</i>						
O&M Building	\$ 3,300	\$ 3,400	\$ -	\$ -	\$ 6,700	\$ -
Solar Panel Removal	\$ 1,311,800	\$ 1,366,500	\$ 455,400	\$ -	\$ 3,133,700	\$ -
Panel Supports/Rack	\$ 1,317,000	\$ 1,371,900	\$ -	\$ -	\$ 2,688,900	\$ -
Battery Containers and Racks	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Electrical & Wiring	\$ 112,900	\$ 117,600	\$ -	\$ -	\$ 230,500	\$ -
Site Restoration	\$ 197,400	\$ 205,600	\$ -	\$ 2,296,400	\$ 2,699,400	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 6,400	\$ -	\$ 6,400	\$ -
Debris	\$ -	\$ -	\$ 3,200	\$ -	\$ 3,200	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (2,092,100)
<b>Subtotal</b>	<b>\$ 2,942,400</b>	<b>\$ 3,065,000</b>	<b>\$ 465,000</b>	<b>\$ 2,296,400</b>	<b>\$ 8,768,800</b>	<b>\$ (2,092,100)</b>
<b>Riverside Solar Subtotal</b>	<b>\$ 2,942,400</b>	<b>\$ 3,065,000</b>	<b>\$ 465,000</b>	<b>\$ 2,296,400</b>	<b>\$ 8,768,800</b>	<b>\$ (2,092,100)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 8,768,800</b>	<b>\$ (2,092,100)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 8,768,800</b>	<b>\$ (2,092,100)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 6,676,700</b>	

**Table A-35**  
**Tampa International**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Tampa International</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 32,800	\$ 34,200	\$ 10,600	\$ -	\$ 77,600	\$ -
Panel Supports/Rack	\$ 329,900	\$ 343,600	\$ -	\$ -	\$ 673,500	\$ -
Electrical & Wiring	\$ 3,400	\$ 3,600	\$ -	\$ -	\$ 7,000	\$ -
Site Restoration	\$ -	\$ -	\$ -	\$ 35,900	\$ 35,900	\$ -
On-site Concrete Crushing and Remova	\$ -	\$ -	\$ 21,500	\$ -	\$ 21,500	\$ -
Debris	\$ -	\$ -	\$ 400	\$ -	\$ 400	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (296,100)
<b>Subtotal</b>	<b>\$ 366,100</b>	<b>\$ 381,400</b>	<b>\$ 32,500</b>	<b>\$ 35,900</b>	<b>\$ 815,900</b>	<b>\$ (296,100)</b>
<b>Tampa International Subtotal</b>	<b>\$ 366,100</b>	<b>\$ 381,400</b>	<b>\$ 32,500</b>	<b>\$ 35,900</b>	<b>\$ 815,900</b>	<b>\$ (296,100)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 815,900</b>	<b>\$ (296,100)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 815,900</b>	<b>\$ (296,100)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 519,800</b>	

**Table A-36**  
**Wimauma Solar**  
**Solar Decommissioning Cost Summary**

	Labor	Material and Equipment	Disposal	Environmental	Total Cost	Scrap Value
<b>Wimauma Solar</b>						
<i>Solar Farm</i>						
Solar Panel Removal	\$ 2,054,900	\$ 2,140,400	\$ 710,000	\$ -	\$ 4,905,300	\$ -
Panel Supports/Rack	\$ 2,942,900	\$ 3,065,500	\$ -	\$ -	\$ 6,008,400	\$ -
Battery Energy Storage System	\$ 149,600	\$ 119,000	\$ 133,300	\$ -	\$ 401,900	\$ -
Electrical & Wiring	\$ 85,400	\$ 89,000	\$ -	\$ -	\$ 174,400	\$ -
Site Restoration	\$ 96,700	\$ 100,800	\$ -	\$ 3,712,900	\$ 3,910,400	\$ -
On-site Concrete Crushing and Removal	\$ -	\$ -	\$ 3,500	\$ -	\$ 3,500	\$ -
Debris	\$ -	\$ -	\$ 7,900	\$ -	\$ 7,900	\$ -
Scrap	\$ -	\$ -	\$ -	\$ -	\$ -	\$ (4,267,300)
<b>Subtotal</b>	<b>\$ 5,330,600</b>	<b>\$ 5,515,900</b>	<b>\$ 854,700</b>	<b>\$ 3,712,900</b>	<b>\$ 15,414,100</b>	<b>\$ (4,267,300)</b>
<b>Wimauma Solar Subtotal</b>	<b>\$ 5,330,600</b>	<b>\$ 5,515,900</b>	<b>\$ 854,700</b>	<b>\$ 3,712,900</b>	<b>\$ 15,414,100</b>	<b>\$ (4,267,300)</b>
<b>TOTAL DECOM COST (CREDIT)</b>					<b>\$ 15,414,100</b>	<b>\$ (4,267,300)</b>
<b>PROJECT INDIRECTS (0%)</b>					<b>\$ -</b>	
<b>CONTINGENCY (0%)</b>					<b>\$ -</b>	
<b>TOTAL PROJECT COST (CREDIT)</b>					<b>\$ 15,414,100</b>	<b>\$ (4,267,300)</b>
<b>TOTAL NET PROJECT COST (CREDIT)</b>					<b>\$ 11,146,800</b>	





[1898andco.com](http://1898andco.com)

## ■ Project Director



## Jeff Kopp, PE

Senior Managing Director, Energy & Utilities Consulting

### Education

B.S. / Civil Engineering

MBA / Business Administration

### Registrations

- Professional Engineer (FL, IL, IN, MO)

22 years with 1898 & Co.

23 years of experience

Visit my [LinkedIn](#) profile.



Jeff is the Managing Director of Utility Consulting at 1898 & Co., part of Burns & McDonnell. He and his team specialize in consulting services for power generation and transmission and distribution projects. This includes power plant decommissioning studies, energy project development, due diligence reviews, resource planning, renewable project development, rate studies and analysis, transmission planning, distribution planning, and grid modernization.

## PROJECT EXPERIENCE

### Decommissioning Study / CenterPoint Energy Indiana South Indiana / 2023

Project director on a decommissioning study for the entire fleet of power generating facilities owned by CenterPoint Energy Indiana South. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plants, natural gas-fired simple and combined cycle units, landfill gas, wind farms, and solar projects. Subsequent to the studies, Jeff will be available to provide written and oral testimony regarding the study findings.

### Decommissioning Study / Tampa Electric Company Florida / 2017

Project director on a decommissioning study for the entire fleet of power generating facilities owned by Tampa Electric. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation includes a coal-fired plant, natural gas-fired simple and combined cycle units, and solar projects. Subsequent to the study, Jeff will be available to provide written and oral testimony in Tampa Electric's rate hearing regarding the study findings.

### Decommissioning Study / Duke Energy

North Carolina, South Carolina, Kentucky, Indiana, Florida / 2022

Project director on a decommissioning study for the entire fleet of power generating facilities owned by Duke Energy Carolinas, Duke Energy Progress, Duke Energy Kentucky, and Duke Energy Florida. The evaluations were performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plants, natural gas-fired simple and combined cycle units, gas fired boilers, hydro-electric plants, and solar projects. Subsequent to the studies, Jeff provided written and oral testimony in Duke Energy rate hearings in and Kentucky regarding the study findings.

JEFF KOPP / PROJECT DIRECTOR

## PROJECT EXPERIENCE

### Decommissioning Study / CenterPoint Energy Indiana South

Indiana / 2022

Project director on a decommissioning study for the coal-fired AB Brown plant owned by CenterPoint Energy Indiana South. The evaluation was performed to determine the cost to demolish the unit and restore the site at the end of its useful life to support regulatory filings. Subsequent to the study, Jeff provided written regarding the study findings.

### Decommissioning Study / Northern Indiana Public Service Co.

Indiana / 2022

Project director on a decommissioning study for the entire fleet of power generating facilities owned by Northern Indiana Public Service Company. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plants, natural gas-fired simple and combined cycle units, hydro-electric plants, wind farms, solar farms, and battery energy storage projects. Subsequent to the studies, Jeff provided written and oral testimony in Duke Energy rate hearings in North Carolina and Kentucky regarding the study findings.

### Decommissioning Study / Evergy

Kansas, Missouri / 2021

Project director on a decommissioning study for the entire fleet of power generating facilities owned by Evergy in the States of Kansas and Missouri. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included several coal-fired plants, natural gas-fired simple and combined cycle units, and wind farms. Subsequent to the study, Jeff is available to provide written and oral testimony in Evergy's rate case hearing regarding the study findings.

### Decommissioning Study / FPL Energy

Florida, Georgia / 2020

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by FPL Energy and Gulf Power in the States of Florida and Georgia. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included several coal-fired plants, natural gas-fired simple and combined cycle units, and solar generating facilities. Subsequent to the study, Jeff

provided written testimony in FPL Energy's rate case hearing regarding the study findings.

### Decommissioning Study / Xcel Energy

Colorado / 2020

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Xcel Energy in the State of Colorado. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included several coal-fired plants, natural gas-fired simple and combined cycle units, and hydroelectric plants. Subsequent to the study, Jeff was available to provide written and oral testimony in Xcel Energy's rate hearing regarding the study findings.

### Decommissioning Study / Apex Clean Energy

New York / 2019

Project manager on a decommissioning study for a wind farm being developed in New York. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support Calpine's application to construct a major electric generating facility under Article 10 of the New York Public Service Law. Subsequent to the study, Jeff provided written testimony in the Article 10 public hearings regarding the study findings.

### Decommissioning Study / Calpine

New York / 2019

Project manager on a decommissioning study for a wind farm being developed in New York. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support Calpine's application to construct a major electric generating facility under Article 10 of the New York Public Service Law. Subsequent to the study, Jeff provided written testimony in the Article 10 public hearings regarding the study findings.

### Decommissioning Study / Southwestern Public Service

Texas, New Mexico / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Southwestern Public Service. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plants, natural gas-fired simple cycle units, and gas fired boiler projects. The report and results are being used in support of depreciation rates as part of the rate case filing. Jeff provided support through the regulatory process with written testimony

JEFF KOPP / PROJECT DIRECTOR

in Southwestern Public Service's rate hearings regarding the study findings.

#### Decommissioning Study / Duke Energy Indiana / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Duke Energy Indiana. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plants, natural gas-fired simple and combined cycle units, solar projects, and a hydro-electric plant. Jeff provided support through the regulatory process with written testimony in Duke Energy Indiana's rate hearing regarding the study findings.

#### Decommissioning Study / Golden Valley Electric Association Alaska / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Golden Valley Electric Association. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included a coal-fired plant, diesel and naphtha fired combustion turbine units, a battery energy storage facility, and a wind farm. Jeff provided written testimony in Golden Valley's Compliance Hearing regarding the retirement of their Healy Unit 1 project. Jeff also provided written testimony in Golden Valley's rate hearing regarding the study findings.

#### Decommissioning Study / Owensboro Municipal Utilities Kentucky / 2018

Project manager on a decommissioning study for coal fired generating facility owned by Owensboro Municipal Utilities. The evaluation was performed to determine the options for retiring the plant and associated costs. Options evaluated included placing one of the units into layup with the potential to restart at a later date, retirement in place, or full demolition and site restoration.

#### Decommissioning Study / Duke Energy Florida / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Duke Energy Florida. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included a coal-fired plant, natural gas-fired simple and combined cycle units, and solar projects. Subsequent to the

study, Jeff provided written testimony in Duke Energy Florida's rate hearing regarding the study findings.

#### Decommissioning Study / Tucson Electric Power Arizona / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Tucson Electric Power. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included a coal-fired plant, natural gas-fired simple and combined cycle units, and solar projects. Subsequent to the study, Jeff was available to provide written and oral testimony in Tucson Electric Powers's rate hearing regarding the study findings.

#### Decommissioning Study / Public Service of New Mexico New Mexico / 2018

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Duke Energy Florida. The evaluation is being performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation includes a coal-fired plant, natural gas-fired simple and combined cycle units, and solar projects.

#### Decommissioning Study / Capital Power Illinois / 2018

Project manager on a decommissioning study for a wind farm being developed in Illinois. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support the county zoning application. Subsequent to the study, Jeff will be available to provide written and oral testimony in the county zoning hearings regarding the study findings.

#### Decommissioning Study / Calpine New York / 2018

Project manager on a decommissioning study for a wind farm being developed in New York. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support Calpine's application to construct a major electric generating facility under Article 10 of the New York Public Service Law. Subsequent to the study, Jeff provided written and oral testimony in the Article 10 public hearings regarding the study findings.

#### Decommissioning Study / Tradewind Energy Illinois / 2018

JEFF KOPP / PROJECT DIRECTOR

Project manager on a decommissioning study for a wind being developed in Illinois. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support the county zoning application. Subsequent to the study, Jeff will be available to provided support for the county zoning hearings regarding the study findings.

**Decommissioning Study / Hawaii Electric Company**  
Hawaii / 2018

Project manager on a decommissioning study for a reciprocating engine plant that was under construction for Hawaii Electric Company. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life.

**Decommissioning Study / EDP Renewables**  
Indiana / 2018

Project manager on a decommissioning study for a wind farm being developed in Indiana. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support the county zoning application. Subsequent to the study, Jeff provided written and oral testimony in the county zoning hearings regarding the study findings.

**Decommissioning Study / EDP Renewables**  
Illinois / 2018

Project manager on a decommissioning study for a wind farm being developed in Illinois. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support the county zoning application. Subsequent to the study, Jeff provided oral testimony in the county zoning hearings regarding the study findings.

**Due Diligence / Centerpoint Energy**  
Indiana / 2017

Project manager for a due diligence evaluation of Vectren's fleet of power plants being considered as part of a potential full acquisition of Vectren by Centerpoint. The evaluation included a technical, environmental, and contractual review of the coal, simple cycle, and wind farm facilities. As part of the project, Jeff presented the results of the study to CenterPoint's board of directors to support their decision making process for the acquisition.

**Due Diligence / PKA AIP**  
Michigan / 2017

Project manager for a due diligence evaluation of a combined cycle power plant being considered for potential equity investment by PKA AIP. The evaluation included a technical, environmental, and contractual review of the plant.

**Decommissioning Study / Tampa Electric Company**  
Florida / 2017

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Tampa Electric. The evaluation is being performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation includes a coal-fired plant, natural gas-fired simple and combined cycle units, and solar projects. Subsequent to the study, Jeff will be available to provide written and oral testimony in Tampa Electric's rate hearing regarding the study findings.

**Decommissioning Asset Retirement Obligation Study / NRG Energy & Clearway Energy**  
Various US Locations / 2017 - 2020

Project manager on a decommissioning study to evaluate the asset retirement obligation costs for numerous renewable energy facilities owned by NRG Energy throughout the United States. The evaluation was performed to determine the costs for any obligations to remove and/or demolish the facilities and equipment and perform environmental remediation and site restoration activities. The study was performed to support compliance with FAS 143 requirements.

**Due Diligence / Confidential Client**  
Northwest / 2017

Project manager for a due diligence evaluation of three natural gas fired combine cycle power plants being considered for potential acquisition. The evaluation included a technical, environmental, and contractual review of the facilities.

**Decommissioning Study / Confidential Client**  
Illinois / 2017

Project manager for a site retirement evaluation to help determine the cost to retire a 600 MW coal-fired project in Illinois at the end of its useful life. Estimates for demolition and site restoration were included in the evaluation. Jeff previously prepared decommissioning study estimates for this plant with the updated study being performed to reflect current pricing and changes in regulations.

JEFF KOPP / PROJECT DIRECTOR

### Decommissioning Study / AEP

Ohio, Indiana / 2017

Project manager on a decommissioning study for two coal fired power plants owned by Ohio Valley Electric Company and Indiana Kentucky Electric Company, both of which AEP is the largest shareholder. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives for purposes of accruing the costs over the life of the plants.

### Decommissioning Study / OGE Energy Corp.

Oklahoma / 2017

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by OGE Energy in Oklahoma. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support depreciation rates. The evaluation included several coal-fired plants, natural gas fired boilers, natural gas-fired simple and combined cycle units, and a wind farm. Subsequent to the study, Jeff provided written testimony, and is currently providing support in replying to discovery requests. Jeff will be available to provide oral testimony in OGE Energy's rate hearing regarding the study findings.

### Decommissioning Study / Duke Energy

North Carolina, South Carolina, Kentucky / 2017

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Duke Energy Carolinas, Duke Energy Progress, and Duke Energy Kentucky. The evaluations were performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included coal-fired plant, natural gas-fired simple and combined cycle units, gas fired boilers, hydro-electric plants, and solar projects. Subsequent to the study, Jeff provided written and oral testimony in Duke Energy rate hearings in North Carolina and Kentucky regarding the study findings.

### Useful Life Assessment / Confidential Client

Southeast / 2017

Project manager on a useful life assessment for a combined cycle power plant for a confidential client. The evaluation was performed to determine the anticipated life of the facility and associated costs to achieve that life. The study supported financial modeling of the facility as part of the utility's portfolio of assets.

### Useful Life Assessment / Confidential Client

Southeast / 2017

Project manager on a useful life assessment for a combined cycle power plant for a confidential client. The evaluation was performed to determine the anticipated life of the facility and associated costs to achieve that life. The study supported financial modeling of the facility as part of the utility's portfolio of assets.

### Decommissioning Study / FPL Energy

Florida / 2015

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by FPL Energy in the State of Florida. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included several coal-fired plants, natural gas-fired simple and combined cycle units, solar generating facilities. Subsequent to the study, Jeff provided written and oral testimony in FPL Energy's rate case hearing regarding the study findings.

### Decommissioning Study / Xcel Energy

Colorado / 2014

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Xcel Energy in the State of Colorado. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives to support regulatory filings. The evaluation included several coal-fired plants, natural gas-fired simple and combined cycle units, hydroelectric plants, and a wind farm. Subsequent to the study, Jeff is provided written and oral testimony in Xcel Energy's rate hearing regarding the study findings.

### Decommissioning Cost Evaluation / Progress Energy Florida

Florida / 2008-2009

Project manager on a site retirement cost evaluation for all the fossil fuel-fired power generating facilities owned by Progress Energy in the state of Florida. The evaluation was performed to determine the costs to demolish the units and restore the sites and included a natural gas-fired steam plants, fuel oil-fired steam plants, natural gas-fired combustion turbines, coal-fired facilities, and combined cycle generating facilities. Subsequent to the study, Jeff provided direct testimony in Progress Energy Florida's rate case regarding the study findings.

JEFF KOPP / PROJECT DIRECTOR

**Decommissioning Asset Retirement Obligation Study /  
NRG Energy**

California / 2016

Project manager on a decommissioning study to evaluate the asset retirement obligation costs for all the fossil fuel-fired power generating facilities owned by NRG Energy in the state of California. The evaluation was performed to determine the costs for any legally obligations to demolish facilities and equipment and perform environmental remediation and site restoration activities. The facilities included a natural gas and fuel oil fired plants consisting of boilers, combustion turbines, and combined cycle generating facilities.

**Due Diligence / Confidential Client**

Northeast / 2016

Project manager for a due diligence evaluation of a portfolio of power generation assets. The assets included gas and oil fired boilers, combined cycle combustion turbines, and simple cycle combustion turbines. The client was considering acquiring an equity stake in the facilities. The evaluation included a technical, environmental, and contractual review of the facilities. The review primarily focused on evaluation of recent repairs to the facilities, remaining life of the equipment, and potential large capital cost requirements to identify key risks or fatal flaws.

**Due Diligence / Confidential Client**

Northeast / 2016

Project manager for a due diligence evaluation of a coal fired power generating facility that was being offered for sale. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the facilities. The review primarily focused on evaluation of the condition of the equipment and facilities, upgrades required to comply with environmental regulations, and other major capital or O&M projects to identify key risks or fatal flaws.

**Due Diligence / Confidential Client**

Northeast / 2016

Project manager for a due diligence evaluation of a combined cycle generating facility under development. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility. The review primarily focused on evaluation of the project costs, schedule, permitting, and other development activities to determine any development risks or fatal flaws.

**Decommissioning Study / PacifiCorp**

Oregon, Washington, Wyoming / 2016

Project manager on a decommissioning study for three wind farms owned by PacifiCorp. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives in support of determining depreciation rates.

**Due Diligence / Confidential Client**

Northeast / 2016

Project manager for a due diligence evaluation of a combined cycle generating facility under development. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility. The review primarily focused on evaluation of the project costs, schedule, permitting, EPC contract, equipment contracts, and other development activities to determine any development risks or fatal flaws.

**Due Diligence / Confidential Client**

Southeast / 2016

Project manager for a due diligence evaluation of a natural gas fired combined cycle power generating facility that was being offered for sale. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the facility. The review primarily focused on evaluation of the condition of the equipment, sufficiency of contractual arrangements, and environmental compliance to identify key risks or fatal flaws

**Decommissioning Study / Big Rivers Electric Cooperative**

Kentucky / 2016

Project manager on a decommissioning study for two coal-fired power generating facilities owned by Big Rivers Electric Cooperative. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives.

**Due Diligence / Confidential Client**

Northeast / 2016

Project manager for a due diligence evaluation of a natural gas fired combined cycle power generating facility that was being offered for sale. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the facility. The review primarily focused on evaluation of the condition of the equipment, sufficiency of contractual arrangements, design issues surrounding recent plant performance challenges, and environmental compliance to identify key risks or fatal flaws.

JEFF KOPP / PROJECT DIRECTOR

### Useful Life Assessment / Confidential Client

Southeast / 2015

Project manager on a useful life assessment for a combined cycle power plant for a confidential client. The evaluation was performed to determine the anticipated life of the facility to support financing of the project associated with acquisition of the facility.

### Decommissioning Study / Nebraska Public Power District

Nebraska / 2015

Project manager on a decommissioning study for five power generating facilities owned by Nebraska Public Power District. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives. The evaluation included two coal-fired plants, a natural gas-fired boiler plant, a combined cycle plant, and a wind farm.

### Decommissioning Study / Lafayette Utilities System

Louisiana / 2015

Project manager on a decommissioning study for a coal fired generating facility in the state of Louisiana. The evaluation was performed to determine the costs for options to retire the units in place or demolish the units and restore the site now that the units are no longer operating. The costs are being used for planning purposes by the client, to determine the preferred decommissioning plan for the plant.

### Decommissioning Study / Colstrip Energy

Montana / 2015

Project manager on a decommissioning study for a coal fired generating facility in the state of Montana. The evaluation was performed to determine the costs to demolish the unit and restore the site at the end of its useful life. The costs were used for planning purposes by the client, to determine the decommissioning funds that need to be accrued throughout the operating life of the facility.

### Due Diligence / Confidential Client

Northeast / 2015

Project manager for a due diligence evaluation of a combined cycle generating facility under development. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility. The review primarily focused on evaluation of the project costs, schedule, permitting, and other development activities to

determine whether the project was economically attractive and determine any development risks or fatal flaws.

### Decommissioning Study / Apex Clean Energy

Various Locations / 2015

Project manager for a site retirement cost evaluation for three proposed wind energy facilities under development. The evaluation was performed to support permitting activities on the facilities.

### Decommissioning Study / Oklahoma Gas & Electric

Oklahoma / 2014

Project manager on a decommissioning study for a power generating facility in the Midwest. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life. The plant was expected to retire within a year or two of the study, and the costs were used for planning purposes by the client.

### Decommissioning Study / Basin Electric Cooperative

North Dakota & Wyoming / 2014

Project manager on a decommissioning study for five power generating facilities in the North Dakota and Wyoming. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful life. The costs are being used for planning purposes by the client.

### Coal Plant Layup / Hoosier Energy

Indiana / 2014

Project manager on the preparation of a plan to place a coal fired generating facility in long term layup reserve status. The project included preparation of three manuals for the implementation of the layup plan, maintaining the plant during the layup period, and reactivating the plant at the end of the layup period. .

### Decommissioning Study / Apex Clean Energy

Illinois / 2014

Project manager for a site retirement cost evaluation for a proposed wind energy facility under development. The evaluation was performed to support permitting activities on the facility.

### Decommissioning Study / Confidential Client

Midwest / 2014

Project manager for a due diligence evaluation of a combined cycle generating facility under development. The client was considering



JEFF KOPP / PROJECT DIRECTOR

acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility. The review primarily focused on evaluation of the project costs, schedule, permitting, and other development activities to determine whether the project was economically attractive and determine any development risks or fatal flaws.

### Due Diligence / Duke Energy

Florida / 2014

Project manager for a due diligence evaluation of the Osprey Energy Center combined cycle generating facility being offered for sale. Duke Energy was considering acquiring the facility from the current owner. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility. Duke successfully acquired the facility and utilized the Independent Engineer's Report prepared by 1898 & Co. to support the regulatory process through acquisition of the facility.

### Due Diligence / Confidential Client

Southeast / 2014

Project manager for a due diligence evaluation of a cogeneration facility being offered for sale. The client was considering acquiring the facility from the current owner. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility, including a review of potential modifications to the facility due to the loss of the steam host and associated costs.

### Due Diligence / Indiana Municipal Power Agency

Indiana / 2014

Project manager for a due diligence evaluation of a coal-fired generating facility being offered for sale. The client was considering acquiring the assets from the current owner. The evaluation includes a technical, environmental, and contractual review of the coal fired generation facility. .

### Due Diligence / Kansas Municipal Power Agency

Missouri / 2014

Project manager for a due diligence evaluation of a combined cycle generating facility being offered for sale. The client was considering acquiring an equity stake in the facility. The evaluation included a technical, environmental, and contractual review of the natural gas fired generation facility.

### Strategic Site Selection Study / Confidential Client

Midwest / 2013

Lead on site selection study for a new natural gas fired combined cycle generating resource in the Midwest. The study included evaluating greenfield and brownfield sites to determine the most attractive sites and the limiting factors to development at each site.

### Strategic Site Selection Study / Confidential Client

Northeast / 2013

Lead on site selection study for a new gas processing facility in the northeast. The study included evaluating potential greenfield locations for a cryogenic gas processing plant to handle wet and dry gas from the Utica and Marcellus Shale areas.

### Site Evaluations / Confidential Client

Southeast / 2013

Lead on the evaluation of three potential sites for a new natural gas fired combined cycle generating facility in the Southeast. The study included reviewing three sites previously selected by the client and ranking those sites relative to one another to determine their suitability for the natural gas-fired generation options under consideration. .

### Decommissioning Study / Arizona Public Service

Arizona / 2013

Project manager on a decommissioning study for a four-steam electric generating facilities in the southwest. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives. The evaluation included two coal-fired plants, and two natural gas and fuel oil fired boilers.

### Decommissioning Study / Confidential Client

Texas / 2013

Lead on a decommissioning study for a coal fired generating facility in Texas. The study included evaluating options to place the plant in reserve shutdown status or completely retire the plant and perform full plant demolition.

### Decommissioning Study / Confidential Client

Upper Midwest / 2013

Project manager on a decommissioning study for a coal fired generating facility in the upper Midwest. The study included phasing the retirement dates of portions of the facility and performing selective demolition as appropriate with full demolition to be complete at the end of useful life of the entire facility. The study also included evaluating potential value of equipment for sale on the secondary market.

JEFF KOPP / PROJECT DIRECTOR

### Decommissioning Study / Confidential Client

Ohio River Valley / 2013

Project manager on a decommissioning study for two coal fired generating facilities in the Ohio River Valley. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful life. The costs are being used for planning purposes by the client.

### Decommissioning Study / EDP Renewables

Illinois / 2013

Project manager on a decommissioning study for a wind farm being developed in New York. The evaluation was performed to determine the costs to demolish the units and restore the site at the end of its useful life to support Calpine's application to construct a major electric generating facility under Article 10 of the New York Public Service Law. Subsequent to the study, Jeff will be available to provide written testimony in the Article 10 public hearings regarding the study findings.

### Strategic Site Selection Study / Confidential Client

Western Kansas / 2012

Lead on a strategic site selection study for a new natural gas fired generation resource in the state of Kansas. The study resulted in the identification of multiple viable site alternatives to support the natural gas-fired generation options under consideration.

### Due Diligence / Confidential Client

Northeast / 2012

Project manager for a due diligence evaluation of a coal-fired generating facility being offered for sale. The client was considering acquiring the assets from the current owner. The evaluation includes a technical, environmental, and contractual review of the coal fired generation facility.

### Due Diligence / Old Dominion Electric Cooperative

Pennsylvania / 2012

Jeff provided support for a due diligence evaluation of a facility under development, that included a 2-on-1 combined cycle power block, being offered for sale. The client was considering acquiring the site from the current owner. The evaluation included a technical, environmental, and contractual review of the combined cycle generation facility. The evaluation included a review of existing agreements and permits in place to facilitate development of the generation resource. The project also included a review of the project capital costs to determine whether the costs were reasonable, and to identify any gaps that may increase the overall project cost.

### Due Diligence / Old Dominion Electric Cooperative

New Jersey / 2012

Project manager for a due diligence evaluation of a facility that was under construction at the time, and was being offered for sale. The client was considering acquiring the 2-on-1 combined cycle power generating facility, from the current owner. The evaluation included a technical, environmental, and contractual review of the including a review of existing agreements and permits in place. The project also included a review of the project capital costs to determine whether the costs were reasonable, and to identify any gaps that may increase the overall project cost.

### Due Diligence / Old Dominion Electric Cooperative

Virginia / 2012

Project manager for a due diligence evaluation of a facility under development, that included a 2-on-1 combined cycle power block, being offered for sale. The client was considering acquiring the site from the current owner. The evaluation included a technical, environmental, and contractual review of the combined cycle generation facility. The evaluation included a review of existing agreements and permits in place to facilitate development of the generation resource. The project also included a review of the project capital costs to determine whether the costs were reasonable, and to identify any gaps that may increase the overall project cost.

### Due Diligence / Confidential Client

Southeast / 2012

Jeff assisted with a due diligence evaluation of a facility that includes two, 2-on-1 combined cycle power blocks, being offered for sale. The client was considering acquiring the assets from the current owner. The evaluation included a technical, environmental, and contractual review of the combined cycle generation facility.

### Development Assistance / Tenaska

Ohio / 2012

Project manager assisting a client with the preparation of a Certificate of Environmental Compatibility and Public Need for conversion of an existing simple cycle facility to combined cycle. The facility includes five combustion turbines, four of which will be converted to two, 2-on-1 combined cycle power blocks. The project includes full preparation of the Certificate of Environmental Compatibility and Public Need application, as well as public meeting support.

JEFF KOPP / PROJECT DIRECTOR

### Repower Assessment / Confidential Client

North Dakota / 2011

Jeff assisted a client with an evaluation comparing the economic viability of retrofitting an existing coal-fired power plant with air quality control system equipment in comparison to replacing the plant with new natural gas fired generation. The project includes preparing capital cost estimates; operating and maintenance cost estimates, and determining the net present value of each alternative evaluate the relative economic attractiveness of each alternative.

The evaluation included a technical, environmental, and contractual review of the combined cycle generation facility.

### Due Diligence Evaluation / Tyr Energy

Florida / 2011

Project manager on a due diligence evaluation of a biomass power generating facility under development by American Renewables. The client was considering an equity investment in the facility. The evaluation included a 100 MW bubbling fluidized bed boiler and steam turbine.

### Decommissioning Study / Progress Energy

North Carolina & South Carolina / 2011

Project manager on a decommissioning study for the entire fleet of power generating facilities owned by Progress Energy Carolinas. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives. The evaluation included several coal-fired plants, as well as several natural gas-fired and fuel oil-fired units.

### Due Diligence Evaluation / Electric Cooperative

Maryland / 2011

Project manager on a due diligence evaluation of a combined cycle facility under development in Maryland. The client was considering acquiring the site and all the development rights for installation of a 2-on-1 combined cycle facility. The evaluation included a review of existing agreements and permits in place to facilitate development of the generation resource.

### Decommissioning Study / Minnesota Power

Minnesota / 2011

Project manager on a decommissioning study for several power generating facilities owned by Minnesota Power. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives. The evaluation included three coal-fired plants and a biomass fired facility.

### Decommissioning Study / Tampa Electric Co.

Florida / 2011

Project manager on a decommissioning study for the power generating facilities owned by Tampa Electric Company. The evaluation was performed to determine the costs to demolish the units and restore the sites at the end of their useful lives. The evaluation included a coal-fired plant, an integrated gasification combined cycle plant, and several natural gas-fired units.

### Strategic Site Selection Study / Old Dominion Electric Cooperative

Virginia, Maryland, Pennsylvania, Delaware / 2011

Project manager on a strategic site selection study for a 750 MW combined cycle facility. The study resulted in the identification of multiple viable site alternatives to support the natural gas-fired generation option under consideration.

### Decommissioning Study / Confidential Client

Illinois / 2011

Project manager for a site retirement evaluation to help determine the cost to retire a 600 MW coal-fired project in Illinois at the end of its useful life. Estimates for demolition and site restoration were included in the evaluation.

### Due Diligence Evaluation / Old Dominion Electric Cooperative

Pennsylvania / 2011

Project manager on a due diligence evaluation of a 2-on-1 combined cycle facility being offered for sale by Liberty Electric in Pennsylvania. The client was considering acquiring the assets from the current owner.

### Repower Assessment / Confidential Client

Minnesota / 2010

Jeff assisted a client with an evaluation comparing the economic viability of retrofitting an existing coal-fired power plant with air quality control system equipment in comparison to replacing the plant with new natural gas fired generation. The project includes preparing capital cost estimates; operating and maintenance cost estimates, and determining

JEFF KOPP / PROJECT DIRECTOR

the net present value of each alternative evaluate the relative economic attractiveness of each alternative.

**Biomass Plant Site Selection Study / Confidential Client**  
Texas / 2010

Project manager for a Site Selection Study for a Biomass project to be located in Texas. The project included ranking of candidate sites to determine a preferred site for development of a 20 MW biomass power generating facility.

**Due Diligence Evaluation / Tyr Energy**  
Multiple Locations / 2010

Project manager on a due diligence evaluation for several natural gas-fired facilities being offered for sale by Tenaska. The client was considering an equity investment in the facilities. The evaluation included four combined cycle facilities and one simple cycle facility.

**Power Plant Valuation Assessment / Basin Electric Power Cooperative**  
North Dakota / 2010

Project manager to provide a valuation assessment of the Antelope Valley Station Unit 2, which is being considered for purchase by Basin Electric Power Cooperative. The project includes valuing the 25 year old 450 MW coal fired unit in current dollars and at specified dates in the future.

**Wind Farm Evaluation / Minnesota Power**  
North Dakota / 2010

Project manager to provide an evaluation of a proposed wind farm development in central North Dakota. The project includes wind resource assessments, conceptual engineering design, capital cost estimates, and estimated busbar costs for development of wind farm project in phases on the land currently under contract.

**Decommissioning Cost Evaluations / Horizon Wind Energy**  
Midwest / 2008-2010

Project manager on multiple site retirement cost evaluations for several proposed wind energy facilities under development by Horizon Wind Energy. The evaluations were performed to support permitting activities on the facilities.

**Due Diligence Evaluation / Tyr Energy**  
Hawaii / 2010

Project manager on a due diligence evaluation for a biomass gasification generating facility under development in Hawaii. The client was considering the facility for investment. The evaluation included a Primenergy gasifier with a net plant output of approximately 12 MW.

**Project Development Assistance / Tradewind Energy**  
Kansas / 2009-2010

Project manager to provide development assistance on a wind farm facility in Southern Kansas. The development assistance includes support on land acquisition efforts for the project, transmission line routing and preliminary design, power collection system preliminary design, and general project development assistance.

**Project Development Assistance / Tradewind Energy**  
Missouri / 2007-2010

Project manager to provide development assistance on two wind turbine facilities in Northern Missouri. The development assistance includes support on land acquisition efforts for the project, transmission line routing and preliminary design, power collection system preliminary design, and general project development assistance.

**Decommissioning Cost Evaluation / Northern Indiana Public Service Co.**  
Indiana / 2008

Project manager on a site retirement cost evaluation for several generating facilities owned by NIPSCO. The evaluation was performed to determine the costs to demolish the units and restore the sites and included several coal-fired facilities and a combined cycle generating facility.

**Due Diligence Evaluation / Grays Harbor Public Utility District**  
Washington / 2008

Project manager on a due diligence evaluation for a biomass-fired cogeneration facility being offered for sale in Washington. The facility evaluated was a paper mill that had been shutdown for several years. The facility included a wood waste fired boiler that provided steam to a steam turbine for electric power generation as well as providing plant process steam.

JEFF KOPP / PROJECT DIRECTOR

### Due Diligence Evaluation / Tyr Energy

New Mexico / 2008

Project manager on a due diligence evaluation for a natural gas-fired power generating facility being offered for sale in New Mexico. The evaluation included two Mitsubishi 501F combustion turbines operating in combined cycle mode.

### Decommissioning Cost Evaluation / Horizon Wind Energy

Illinois / 2008

Project manager on a site retirement cost evaluation for a wind farm being proposed by Horizon Wind Energy in Illinois. The evaluation was performed to determine the costs to demolish the units and restore the sites to meet the county zoning requirements.

### Due Diligence Evaluation / Tyr Energy

Western U.S. / 2008

Project manager on a due diligence evaluation for several natural gas-fired power generating facilities being offered for sale throughout the western United States. The evaluation included several GE LM6000 combustion turbines operating in simple cycle mode, several GE LM6000 combustion turbines operating in combined cycle mode, one GE 7EA combustion turbine operating in combined cycle mode, and one GE 7FA combustion turbine operating in simple cycle mode.

### Due Diligence Evaluation / Tyr Energy

Virginia / 2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Virginia. The evaluation included 7 GE LM6000 fuel oil fired combustion turbines operating in simple cycle mode.

### Due Diligence Evaluation / Tyr Energy

Colorado / 2007

Project manager on a due diligence evaluation for 5 GE LM6000 combustion turbines operating in combined cycle cogeneration mode with 2 steam turbines. The facility includes a greenhouse that serves as the plant's thermal host for cogeneration operations.

### Project Development Assistance / Mesa Wind Power

Texas / 2007

Jeff provided development assistance on a 4,000 MW wind turbine facility located in the panhandle of Texas. The development assistance includes pro forma economic modeling of the project.

### Due Diligence Evaluation / Kelson Energy

Ohio / 2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Ohio. The evaluation included a partially constructed 2x1 Siemens Westinghouse 7FA combined cycle generating facility.

### Due Diligence Evaluation / Grand River Dam Authority

Oklahoma / 2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Oklahoma. The evaluation included a 4x2 GE 7FA combined cycle generating facility.

### Due Diligence Evaluation / Brazos Electric Power Cooperative

Texas / 2007

Project manager on a due diligence evaluation for the purchase of an equity share of a generating facility being constructed in Texas. The evaluation included an 890 MW supercritical pulverized coal fired generating facility.

### Due Diligence Evaluation / Tyr Energy

Florida / 2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Florida. The evaluation included 3 GE 7FA combustion turbines operating in simple cycle mode.

### Cost Estimate Preparation / Direct Energy

Texas / 2007

Project manager for the preparation of planning level cost estimates for a new combined cycle facility to be constructed in Texas.

### Due Diligence Evaluation / Tyr Energy

Various U.S Locations / 2007

Project manager on a due diligence evaluation for several generating facilities being offered for sale throughout the U.S. The evaluation included a coal, natural gas, and wind power facilities.

JEFF KOPP / PROJECT DIRECTOR

**Owner's Engineer Services / Grays Harbor PUD**  
Washington / 2007

Project manager on an owner's engineer project to evaluate the plans for installation of a refurbished steam turbine at a paper mill. The evaluation included the review of the design for the installation of a 7 MW steam turbine.

**Decommissioning Cost Evaluation / Tyr Energy**  
Various U.S Locations / 2007

Project manager on a site retirement cost evaluation for several generating facilities owned by Tyr Energy. The evaluation was performed to satisfy FASB 143 accounting standards and included a simple cycle and combined cycle generating facilities.

**Due Diligence Evaluation / Tyr Energy**  
Virginia / 2006-2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Virginia. The evaluation included a 240 MW subcritical pulverized coal fired facility.

**Due Diligence Evaluation / Brazos Electric Power Cooperative**  
Texas / 2006

Project manager on a due diligence evaluation for a generating facility being offered for sale in Texas. The evaluation included a 1x1 GE 7FA combined cycle generating facility and 2 GE 7FA combustion turbines operating in simple cycle mode.

**Due Diligence Evaluation / Kelson Energy**  
Ohio / 2007

Project manager on a due diligence evaluation for a generating facility being offered for sale in Ohio. The evaluation included a partially constructed 2x1 Siemens Westinghouse 7FA combined cycle generating facility.

**Generation Alternatives Study / Ottertail Power Company**  
North Dakota / 2006

Project manager on a Generation Alternatives Study for the addition of a new 600 MW coal fired unit at an existing coal fired facility. The study includes a pro forma analysis of the technologies considered.

**Technology Assessment / Minnesota Power**  
South Dakota / 2006

Assisted with a technology assessment for the addition of a new 500 MW coal fired unit at an existing coal fired facility. The study includes a pro forma analysis of the technologies considered.

**Technology Assessment & Feasibility Study / Ottertail Power Co.**  
Minnesota / 2006

Project manager on a feasibility study and technology assessment for the addition of a new 500 MW coal fired unit at an existing coal fired facility. The study includes conceptual site layouts, cost estimates, performance estimates, and water balances.

**Project Development Assistance / Tradewind Energy**  
Kansas / 2005-2006

Project manager to provide development assistance on a 250MW wind turbine facility in Central Kansas. The development assistance includes conceptual design and technical support for the development phase of the project.

**Siting Study & Technology Assessment / Arizona Public Service**  
Arizona/New Mexico / 2005-2006

Assisted with a siting study and technology assessment for a 1,800 MW coal fired facility in Arizona and Northwestern New Mexico. Development resulted in the identification of multiple viable site alternatives to support coal-fired generation options.

**Due Diligence Evaluation / Tyr Energy**  
California / 2005-2006

Project manager on a due diligence evaluation for four generating facilities being offered for sale in California. The evaluation included simple cycle facilities consisting of Pratt & Whitney FT8 Twinpacs.

**Professional Services: 2005-2006**

**Waste-to-Energy Feasibility Study / CPS Energy**  
Texas / 2005

Assisted with a feasibility study for a new waste-to-energy facility in the State of Texas. The study included a pro forma analysis of the facility considered.

JEFF KOPP / PROJECT DIRECTOR

### Due Diligence Evaluation / Tyr Energy

Oklahoma / 2006

Project manager on a due diligence evaluation for a generating facility being offered for sale in Oklahoma. The evaluation included a simple cycle facility consisting of four General Electric 7EA turbines.

### Due Diligence Evaluation / Cinergy

Indiana / 2005

Project manager on a due diligence evaluation for a generating facility being offered for sale in Indiana. The evaluation included a simple cycle facility consisting of four Siemens Westinghouse 501D5A turbines.

### Due Diligence Evaluation / kRoad Power

Various Locations / 2003-2004

Project manager on due diligence evaluations for several generating facilities being offered for sale throughout the United States. The evaluations included four combined cycle plants utilizing Siemens Westinghouse 501G turbines.

### Due Diligence Evaluation / kRoad Power

Various Locations / 2003

Project manager on due diligence evaluations for several generating facilities being offered for sale by Duke Energy. The evaluations included two combined cycle plants and one simple cycle plant utilizing General Electric 7FA turbines and General Electric 7EA turbines respectively.

### Decommissioning Cost Evaluation / Old Dominion Electric Cooperative

Maryland/Virginia / 2002-2004

Project manager on several site retirement evaluations to help determine the cost to retire the facilities at the end of their useful life. The evaluations included simple cycle plants utilizing General Electric 7FA turbines and Caterpillar Diesel Gensets. Estimates for demolition and site restoration were included.

### Decommissioning Cost Evaluation / Western Farmers Electric Cooperative

Oklahoma / 2004

Project manager on a site retirement evaluation to determine the approximate cost to retire the facilities, prepare demolition contract documents, and evaluate bids. The evaluation included a dual fuel genset site.

### Decommissioning Cost Evaluation / Panda Energy

North Carolina / 2003

Project manager on a site retirement evaluation to help determine the cost to retire the Panda-Rosemary Project at the end of its useful life. The evaluation included a combined cycle cogeneration facility in Roanoke Rapids, North Carolina. Estimates for demolition and site restoration were included in the evaluation.

### Independent Engineer's Report / Panda Energy

North Carolina / 2003-2004

Produced an Independent Engineer's Report for the Panda-Rosemary Project. The report included a due diligence evaluation of plant performance and financial assessment of a combined cycle cogeneration facility in Roanoke Rapids, North Carolina.

### Decommissioning Cost Evaluation / Sempra Energy

Arizona / 2003

Provided a site retirement evaluation to help determine the cost to retire the Mesquite Energy Generating Facility at the end of its useful life. The evaluation included a combined cycle plant near Phoenix, Arizona. Estimates for demolition and site restoration were included in the evaluation.

### Feasibility Study / Northeast Utility Service Corp

New Hampshire / 2004

Assisted with a feasibility study to replace an existing coal-fired unit with a new coal fired unit. The study included the installation of a single 600 MW unit in New Hampshire. A pro forma analysis of the new unit was prepared and benchmarked against a pro forma analysis for the existing unit.

### Technology Assessment & Feasibility Study / Ottertail Power Corp

South Dakota / 2006

Assisted with a technology assessment and feasibility study for a new coal-fired generation facility in South Dakota. The study included a pro forma analysis of the alternative technologies considered.

### Waste-to-Energy Feasibility Study / CPS Energy

Texas / 2005

Assisted with a feasibility study for a new waste-to-energy facility in the State of Texas. The study included a pro forma analysis of the facility considered.

JEFF KOPP / PROJECT DIRECTOR

Technology Assessment & Feasibility Study / Progress  
Energy

Florida / 2004

Assisted with a technology assessment and feasibility study for new solid fuel fired generation in the State of Florida. The study included a pro forma analysis of the alternative technologies considered.

Resources Corporation Project Development Assistance  
/ Peoples Energy

Oregon / 2001-2004

Provided project development assistance for a 1,200 MW combined cycle power plant in Oregon. Mr. Kopp assisted in the preparation of an Energy Facility Site Certificate including preliminary engineering design, preparation and review of written exhibits, and public presentation support.

Project Development Assistance / Peoples Energy  
Resources Corporation

New Mexico / 2001-2004

Provided project development assistance for a simple cycle power plant in New Mexico. Mr. Kopp provided preliminary engineering design and project development assistance. This included preparing preliminary site design drawings that were approved by the county zoning commission during the site design review process as well as public presentation support.



■ Testimony Experience

**Jeff Kopp, PE**

Senior Managing Director – Energy & Utilities Consulting

Regulatory Agency	Docket No.	Client Represented	Subject
North Carolina Utilities Commission	Docket No. E-7, Sub 1276	Duke Energy Carolinas	Rate Case – Decommissioning Costs
The State Corporation Commission of the State of Kansas	Docket No. 23-EKCE-775-RTS	Evergy Metro, Inc., Evergy Kansas Central, Inc. and Evergy Kansas South, Inc.	Rate Case – Decommissioning Costs
Kentucky Public Service Commission	Case No. 2022-00372	Duke Energy Kentucky	Rate Case – Decommissioning Costs
New Mexico Public Regulation Commission	Case No. 22-00286-UT	Southwestern Public Service Company	Rate Case – Decommissioning Costs
Public Utility Commission of Texas	PUC Docket No. 54634	Southwestern Public Service Company	Rate Case – Decommissioning Costs
Public Service Commission of the State of Missouri	Case No. ER-2022-0129	Evergy Missouri Metro	Rate Case – Decommissioning Costs
Indiana Utility Regulatory Commission	Cause No. 45772	Northern Indiana Public Service Co.	Rate Case – Decommissioning Costs
Indiana Utility Regulatory Commission	Cause No. 45722	Centerpoint Energy Indiana South	Securitization Filing - Decommissioning Costs
Public Service Commission of the State of Missouri	Case No. ER-2022-0129	Evergy Missouri Metro	Rate Case – Decommissioning Costs
Public Service Commission of the State of Missouri	Case No. ER-2022-0130	Evergy Missouri West	Rate Case – Decommissioning Costs
Florida Public Service Commission	Docket No. 20210015-EI	Florida Power & Light Company	Rate Case – Decommissioning Costs
Florida Public Service Commission	Docket No. 20210016-EI	Duke Energy Florida	Rate Case – Decommissioning Costs
Florida Public Service Commission	Docket No. 20200264-EI	Tampa Electric Company	Rate Case – Decommissioning Costs
Kentucky Public Service Commission	2019-00269	Big Rivers Electric Corporation	Enforcement of Rate and Service Standards - Decommissioning
Public Utility Commission of Texas	PUC Docket No. 49831	Southwestern Public Service Company	Rate Case – Decommissioning Costs
New Mexico Public Regulation Commission	Case No. 19-00170-UT	Southwestern Public Service Company	Rate Case – Decommissioning Costs
Indiana Utility Regulatory Commission	Cause No. 45253	Duke Energy Indiana	Rate Case – Decommissioning Costs
The Corporation Commission of the State of Oklahoma	PUD 201800140	Oklahoma Gas and Electric	Rate Case – Decommissioning Costs
The Regulatory Commission of Alaska	U-18-010	Golden Valley Electric Association	Retirement Report for Healy Unit 1 – Decommissioning Costs
Florida Public Service Commission	090079-EI	Progress Energy Florida	Rate Case – Decommissioning Costs

■ **Testimony Experience**

**Jeff Kopp, PE**

Senior Managing Director – Energy & Utilities Consulting

Regulatory Agency	Docket No.	Client Represented	Subject
Minnesota Public Utilities Commission	E017/M-10-1082	Otter Tail Power Company	Advanced Determination of Prudence – AQCS Upgrades
Public Service Commission of the State of North Dakota	PU-11-165	Otter Tail Power Company	Advanced Determination of Prudence – AQCS Upgrades
Public Utilities Commission of the State of Colorado	14AL-0660E	Public Service Company of Colorado	Rate Case – Decommissioning Costs
Public Utilities Commission of the State of Colorado	16A-0231E	Public Service Company of Colorado	2016 Revised Depreciation Rates
Florida Public Service Commission	160021-EI; 160062-EI	Florida Power & Light Company	Rate Case – Decommissioning Costs
Kentucky Public Service Commission	2017-00321	Duke Energy Kentucky	Rate Case – Decommissioning Costs
North Carolina Utilities Commission	Docket No. E-2, Sub 1142	Duke Energy Progress	Rate Case – Decommissioning Costs
North Carolina Utilities Commission	Docket No. E-7, Sub 1146	Duke Energy Carolinas	Rate Case – Decommissioning Costs
Corporation Commission of Oklahoma	Cause No. PUD 201700496	Oklahoma Gas and Electric	Rate Case – Decommissioning Costs