

RECEIVED-FPSC
09 JUN 22 AM 9:18
COMMISSION
CLERK

TLP WATER, INC.
12315 U.S. HIGHWAY 441
TAVARES, FLORIDA 32778

090244-WU

Docket No. 090244
June 16, 2009
Re; Letter dated April 3, 2009
Water Transmission & Distribution (etc) Infrastructure Projects

A copy of this letter has just reached us – we are not yet regulated – and are trying to catch up to information requested items as we are made aware of them.

We are a class 5D Community Water System.
The age of our distribution system dates back to the 1940's. We do not have exact dates as to the installation of the same, we can only go by the documents governing the distribution of water, which documents are dated 1948.

Beginning at the water treatment facility:
The first 1,000 ft (approx.) is of the 1940's and is 2" steel
The next approx. 1300 ft is a 2" pvc ASTM 1785 installed in 2007
The final approx. 600 ft is 1" soft copper
There are two canal crossings connecting the last 600 ft and they are both 1". One is soft copper and the other is flexible pvc.
Installed in the 1950's

COM _____
ECR / Over the next 5 years, if we can access funding (loan/grant) we
GCL / will replace all of the distribution system with PVC lines and the
OPC _____ approx. cost will be \$400,000.00.

RCP _____
SSC _____ Respectfully
SGA _____ William Carey - President
ADM _____
CLK _____ *William Carey*

DOCUMENT NUMBER-DATE
06159 JUN 22 8
FPSC-COMMISSION STAFF